

Characterizing NGC 6383: Study of fundamental properties, pre-main sequence stars, mass segregation, and age using *Gaia* DR3 and 2MASS

L. M. Pulgar-Escobar^{1*}, N. A. Henríquez-Salgado¹, R. E. Mennickent¹, and Pierluigi Cerulo²

¹ Departamento de Astronomía, Universidad de Concepción, Casilla 160-C, Concepción, Chile

² Departamento de Ingeniería Informática y Ciencias de la Computación, Universidad de Concepción, Chile

Received XXXX; accepted YYYY

ABSTRACT

Context. This study is focused on the young open cluster NGC 6383, situated in the Carina-Sagittarius arm within the Sh 2-012 star-formation region. Previous studies have provided estimates of the distance, age, and structural properties of the cluster. The presence of pre-main sequence (PMS) and low-mass stars, combined with *Gaia* DR3 and 2MASS data, makes NGC 6383 a compelling target for a refined characterization.

Aims. We aim to identify cluster members, determine the fundamental parameters, assess the mass segregation, and derive the age and distance of NGC 6383 from *Gaia* DR3 and 2MASS data.

Methods. We employed Bayesian analysis and machine-learning techniques, including Hierarchical Density-Based Spatial Clustering of Applications with Noise (HDBSCAN) for member identification, PyMC for the Bayesian modeling, the Sagitta neural network for the identification and age estimation of PMS stars, and ASteCA for the isochrone fitting.

Results. We identified 321 likely cluster candidates, with $\tilde{p} > 0.5$, and used a reference sample of 254 sources with $\tilde{p} \geq 0.6$ to derive the cluster parameters. The mode cluster age is ≈ 3.5 Myr, with $\log(\text{age yr}^{-1}) = 6.55^{+0.40}_{-0.20}$ (with the uncertainty dominated by PMS model systematics that ~~are active~~ ~~act~~ toward older ages) and the distance is 1.11 ± 0.06 kpc. The core radius is $1.96^{+0.19}_{-0.16}$ arcmin ($0.63^{+0.06}_{-0.05}$ pc); the King outer radius, measured on the only extraction that reaches a fitted background annulus beyond the cluster (70 arcmin), is 54^{+7}_{-11} arcmin ($17.4^{+2.3}_{-3.6}$ pc). This posterior is truncated from above by the adopted prior bound, so we report it as a model-dependent outer scale. Given the cluster's dynamical youth (age ≈ 0.14 of the half-mass relaxation time), the mass segregation of binary stars, which is conditional on the membership of the outer low-mass candidates, is consistent with a primordial or near-primordial origin. The color-magnitude diagram (CMD) shows a well-defined main sequence and a population of PMS stars, whose bulk lies between the 1.6 and 6.3 Myr isochrones, consistent with a recent, possibly extended star formation episode. The software used for this investigation has been released with the paper.

Conclusions. Combining machine-learning membership with Bayesian parameter estimation, our analysis provides updated parameters for NGC 6383, an apparent age spread consistent with recent, possibly extended star formation, and a segregation pattern. This pattern, ~~which~~ is conditional on the membership of the outer low-mass candidates, ~~is~~ consistent with a primordial origin or with rapid early dynamical segregation (near-primordial).

Key words. techniques: photometric – parallaxes – proper motions – stars: distances – stars: pre-main sequence – open clusters and associations: individual: NGC 6383

1. Introduction

Membership determination underpins any star-cluster characterization: distances, ages, and structural parameters are only as reliable as the member list they rely on. Methods have evolved from early spectroscopic and photometric studies (e.g., Trumpler 1930; Sanford 1949; Lindoff 1968; Fitzgerald et al. 1978) to multi-parameter membership analyses (Pandey et al. 1989; Battinelli & Capuzzo-Dolcetta 1991; Kharchenko et al. 2005; Paunzen et al. 2007; Aidelman et al. 2018), whose differing assumptions can return discrepant member lists for the same cluster. Bayesian and machine-learning approaches provide a complementary route that makes the selection criteria explicit and reproducible.

NGC 6383¹ is a young open cluster located in the Carina-Sagittarius arm, within the Sh 2-012 star-formation region (Sharpless 1959). It is commonly associated with the broader Sgr OB1 star-forming complex, together with the open clusters NGC 6530 and NGC 6531 (Rauw & De Becker 2008). The Galactic coordinates are $\ell = 355.68^\circ$ and $b = 0.05^\circ$ (Conrad et al. 2017). The distance to the cluster has been estimated by various authors, ranging from an upper limit of 2.13 kpc (Trumpler 1930) to lower limits of 0.76 kpc (Sanford 1949) and 0.83 kpc (Aidelman et al. 2018). The cluster spans an angular size of 20.0 arcmin (Morales et al. 2013) and is estimated to be between 1.70 and 5.00 Myr old (Fitzgerald et al. 1978; Pandey et al. 1989; Kharchenko et al. 2005; Paunzen et al. 2007), although

¹ NGC 6383, also known as NGC 6374 in the New General Catalog (Rauw & De Becker 2008) and classified as Collinder 334 and Collinder 335 in the Collinder catalog, was initially misclassified in the original Collinder catalog (Collinder 1931).

* E-mail: lescobar2019@udec.cl

Lindoff (1968) and Battinelli & Capuzzo-Dolcetta (1991) estimated ages of ~ 20 Myr. The reddening $E(B - V) = 0.320 \pm 0.020$ derived by Rauw & De Becker (2008) aligns with estimates from previous authors (Becker & Fenkart 1971; Fitzgerald et al. 1978; Lloyd Evans 1978; The et al. 1985; Pandey et al. 1989; Feinstein 1994; Paurzen et al. 2007), but differs from Aidelman et al. (2018), who determined a reddening of $E(B - V) = 0.51 \pm 0.03$. This reddening is due to a surrounding large shell-structured ionized HII region with a radius of approximately 1.00° .

HD 159176, a double-lined spectroscopic binary composed of O7V-type stars located in the projected center of the cluster, is responsible for ionizing the HII region (Penny et al. 2016). The estimated age of HD 159176 is 2.3–2.7 Myr (Rauw et al. 2010), in agreement with the earlier 2.8 ± 0.5 Myr of Fitzgerald et al. (1978). Rauw et al. (2010) found that the age of the most likely low-mass pre-main sequence (PMS) candidates, 2–3 Myr, is in reasonable agreement with the estimated age of HD 159176, consistent with a common star-formation event if the binary is assumed to be a cluster member. Furthermore, Fitzgerald et al. (1978) proposed that HD 159176 initiated star formation in the cluster’s core and beyond.

In a study by Aidelman et al. (2018), the authors hypothesized that if their star No. 6 has begun to evolve and if HD 159176 is a blue straggler, the age of the cluster would be estimated between 6.00 and 10.0 Myr. We treat this interpretation with caution because it depends on the membership and evolutionary status of HD 159176; spectroscopic studies classify the system as an O-type main sequence binary (Stickland et al. 1993; Linder et al. 2007; Penny et al. 2016). The reported parameters span wide ranges, reflecting the diversity of the methods used to derive them. The cluster hosts sources that have recently entered the main sequence track, while PMS stars are also present (Kalari 2019), leading to considerable debate regarding the cluster’s age. A summary of the historical results can be seen in Table A.1.

Relative to the *Gaia*-era survey catalogs (Cantat-Gaudin et al. 2020; He et al. 2022; Hunt & Reffert 2024), which provide membership and bulk parameters, and to the $H\alpha$ /classical T-Tauri star (CTTS) studies (Rauw et al. 2010; Kalari 2019), this work adds a quantified mass-segregation analysis including binaries, a PMS census combining Sagitta with a young stellar object (YSO) fraction and an $H\alpha$ cross-match, an explicit search-window sensitivity study of the membership and structural parameters, and a released, reusable pipeline.

This paper is structured as follows: Sect. 2 describes the *Gaia* DR3 and 2MASS data and their preprocessing. Section 3 presents the analysis pipeline, the membership determination with the Hierarchical Density-Based Spatial Clustering of Applications with Noise (HDBSCAN), and the resulting member catalog. Sections 4 and 5 give the astrometric parameters (parallax, distance, proper motions, radial velocities, and center) and the cluster structure, each derived immediately after the corresponding method is described. Section 6 covers the isochrone-based age, extinction, and metallicity, and the PMS content. Section 7 presents the luminosity function, stellar masses, mass segregation, and the dynamical state. Section 8 compares our results with previous studies, and Sect. 9 summarizes the conclusions. The photometric system adopted includes the *Gaia* DR3 photometric bands (G, G_{BP}, G_{RP}) and the Two Micron All Sky Survey (2MASS) bands (J, H, K_s).

2. Data

We acquired data from the *Gaia* third Data Release (DR3) (Gaia Collaboration et al. 2016, 2023), executing a cone search of 40.0 arcmin radius centered on $(\alpha, \delta) = (263.6715^\circ, -32.5773^\circ)$ (ICRS) in the *Gaia* archive, which yielded 23740 sources. The query restricted the selection to parallaxes between 0.750 and 1.10 mas, based on the limits established in Pulgar-Escobar & Henríquez-Salgado (2024).

To enhance data reliability, we applied the astrometric fidelity parameter from Rybizki et al. (2022). This parameter, derived from a neural network analysis of 17 *Gaia* catalog metrics, assesses the trustworthiness of the astrometric solution. Sources with an astrometric fidelity above 0.5 were retained, narrowing the selection to 15480 sources, which represent 65% of the initial dataset.

Subsequent refinement ensured the inclusion of only sources for which all parameters (α, δ, ℓ, b), proper motions ($\mu_{\alpha*}, \mu_\delta$), parallax (ϖ), and magnitudes (G, G_{BP}, G_{RP}) were available, reducing the dataset to 15276 sources. Systematic parallax offsets identified in Lindegren et al. (2021a) were corrected using the *gaiadr3-zeropoint* package. Moreover, to address the bias in proper motion for bright sources ($G < 13$ mag), as discussed in Cantat-Gaudin & Brandt (2021), we applied a magnitude-based correction for sources with $G = 11$ –13 mag, compensating for up to $80 \mu\text{as yr}^{-1}$ discrepancy between the frames of reference for bright and faint sources.

We also obtained the J, H , and K_s magnitudes from 2MASS (Skrutskie et al. 2006). A left-join cross-match² was performed using the pre-computed *Gaia* DR3 cross-match (Marrese et al. 2022), with the `tmass_psc_xsc_best_neighbour` table and a separation ≤ 0.3 arcsec, giving 5333 cross-matched sources.

3. Analysis framework and cluster membership

Every result below rests on the member list, which is therefore derived first, together with its dependence on the clustering configuration. Section 3.1 sets out the pipeline and the role of each tool, Sect. 3.2 the membership statistic and its marginalization over the hyperparameters, and Sect. 3.3 the resulting catalog and its behavior under a wider search field.

3.1. The EROTICA pipeline

Estimation, Recovery & Optimization, together with Inference, for Cluster Analysis (EROTICA)³ is the open-source Python suite developed for this work. The version used here was released under the earlier name COSMIC and was renamed to avoid a collision with the `cosmic-popsynth` binary-population code. It chains the membership determination and the Bayesian parameter estimation described below into a single reproducible pipeline, using PyMC⁴ (Abril-Pla et al. 2023) for all Bayesian models.

The analysis proceeds in five steps, each performed by a dedicated, publicly available tool. (i) Cluster members are identified as an over-density in the proper-motion plane with the hierarchical density-based clustering algorithm HDBSCAN⁵ (Campello et al. 2013; McInnes et al. 2017) (Sect. 3.2). (ii)

² The left join keeps all *Gaia* sources and appends the available 2MASS data for those with a counterpart, preserving the original 15276 sources.

³ <https://doi.org/10.5281/zenodo.21769959>

⁴ <https://www.pymc.io>

⁵ <https://hdbscan.readthedocs.io>

From the resulting members, the mean parallax and distance, the mean proper motion, and the King structural parameters are inferred with Bayesian models sampled with the No-U-Turn Sampler (NUTS; Hoffman & Gelman 2014). NUTS is a Hamiltonian Monte Carlo variant that adapts its trajectory length by terminating when the path begins to fold back on itself, and it explores high-dimensional posteriors efficiently without the tuning constraints of Metropolis-Hastings or Gibbs sampling (Abril-Pla et al. 2023). (iii) The cluster center is located with a weighted kernel density estimate from scikit-learn⁶ (Pedregosa et al. 2011). (iv) The age, metallicity, extinction, and distance modulus are obtained by Bayesian isochrone fitting of the member photometry with the Automated Stellar Cluster Analysis (ASteCA)⁷ (Perren et al. 2015) (Sect. 6.1); because the synthetic-cluster forward model is called as an external routine and exposes no derivative with respect to the fitted parameters, this model is sampled with the gradient-free differential-evolution Metropolis ensemble sampler (DEMetropolis; ter Braak 2006) instead of NUTS. (v) Finally, the PMS content of the membership is characterized with the Sagitta neural network⁸ (McBride et al. 2021) (Sect. 6.2). Each step operates on the output of the previous one: the HDBSCAN membership defines the sample on which all subsequent astrometric, structural, photometric, and PMS analyses are performed.

All NUTS-based models were run with four chains of 2000 draws after 2000 tuning steps and satisfy the standard convergence criteria (Vehtari et al. 2021): the rank-normalized $\hat{R}$, which compares the between- and within-chain variances and approaches unity when all chains sample the same posterior, is ≤ 1.005 for every parameter (recommended: < 1.01); the bulk and tail effective sample sizes (ESS), namely, the number of effectively independent draws available for the posterior center and its quantile extremes after accounting for autocorrelation, are above 1200 (recommended: > 400); there are no divergent transitions (numerical failures of the Hamiltonian integrator that can bias the sampled posterior); and the energy Bayesian fraction of missing information (E-BFMI; Betancourt 2016), which measures how efficiently the sampler explores the posterior energy distribution, is above 0.79, well clear of the empirical ~ 0.3 level below which exploration becomes unreliable (Betancourt 2017). The DEMetropolis isochrone fit (300 chains of 1000 draws after 1500 tuning steps) does not meet these criteria: its rank-normalized $\hat{R}$ for $\log(\text{age})$ is far from unity and the bulk ESS corresponds to about one effective draw per chain, so the ensemble is not a converged sample from the posterior. The posterior summaries are stable under random half-ensemble bootstraps (mode scatter 0.08 dex in $\log(\text{age})$ and 0.03 mag in distance modulus), but that stability is not evidence of convergence: resampling the same chains cannot reveal that they have not mixed. We therefore do not treat the width of this posterior as a measurement; the age interval adopted in Sect. 6.1 is set instead by the PMS model systematics and the judgment discussed there.

Unless stated otherwise, the values below are derived for the $\bar{p} \geq 0.6$ reference sample (the membership pseudo-probability, $\bar{p}$, is defined in Sect. 3.2), with the point estimator (mode or median) stated where each fit is described. Table 1 summarizes the parameters derived in the following sections.

Table 1. Summary of derived parameters for NGC 6383, for the $\bar{p} \geq 0.6$ reference sample.

Parameter	Value	Unit
Distance (parallax-based)	1.11 ± 0.06	kpc
Distance (from distance modulus)	1.15 ± 0.05	kpc
Distance modulus	10.30 ± 0.09	mag
Age	$3.5^{+5.4}_{-1.3}$	Myr
$\log(\text{age yr}^{-1})$	$6.55^{+0.40}_{-0.20}$	...
Isochrones enclosing most PMS stars	$1.6\text{--}6.3$	Myr
Metallicity (Z)	0.024 ± 0.008	...
Parallax (ϖ)	0.908 ± 0.046	mas
Reference sample	254	stars
Absorption (A_V)	1.24 ± 0.26	mag
Galactocentric distance R_{gc}	7.19 ± 0.06	kpc
Core radius (R_c)	$1.96^{+0.19}_{-0.16}$	arcmin
Background (b)	0.011 ± 0.007	stars arcmin ⁻²
King outer radius (R_t)	54^{+7}_{-11}	arcmin
Center density (k)	$4.92^{+0.43}_{-0.31}$	stars arcmin ⁻²
Hill radius	33.6 ± 2.2	arcmin
Gravitational bound radius	42.5 ± 1.6	arcmin
Cluster center R.A.	263.683 ± 0.112	deg
Cluster center Dec.	-32.584 ± 0.112	deg
Proper motion R.A.	2.542 ± 0.152	mas yr ⁻¹
Proper motion Dec.	-1.713 ± 0.138	mas yr ⁻¹
Half-mass relaxation time	24.7 ± 7.6	Myr
Radial velocity	-9.4 ± 32.1	km s ⁻¹
Concentration parameter (C)	$1.43^{+0.07}_{-0.10}$	...
Structure parameter (Q)	1.03 ± 0.03	...
Mean stellar mass $\langle m \rangle$	1.31 ± 0.10	$M_{\odot}$
Most massive star	13.56 ± 3.25	$M_{\odot}$
Young stellar objects (YSOs)	53/193	stars
Y_{frac}	$0.275^{+0.067}_{-0.058}$	...
Minimum segregation time	2.38 ± 0.95	Myr

Notes. Unless otherwise stated, the quoted uncertainties are the 1σ posterior uncertainty or the 1σ dispersion of the relevant member distribution. Five quantities come from the DEMetropolis isochrone ensemble, described in Sect. 3.1, which is not a converged sample from the posterior: the age, distance modulus, distance derived from it, metallicity, and absorption. Their quoted intervals are therefore not posterior credible widths in the sense used elsewhere in this table. For the age, we replaced the width outright with the range given in Sect. 6.1, whose upper bound is set by the choice of PMS model family and whose lower bound is a stated judgment. For the remaining four the quoted $\pm$ is the marginal spread of that ensemble and should be read as an indication of scale rather than as a calibrated uncertainty; the half-ensemble bootstrap scatter quoted in Sect. 3.1 (0.03 mag in distance modulus) is the more conservative guide. For the astrometric quantities, the proper-motion uncertainties are the observed member dispersions, and the parallax uncertainty is the 1σ dispersion of the subsample with $\delta\varpi/\varpi < 0.1$; the smaller errors on the mean are given in the text where relevant. The Y_{frac} uncertainties are the 95% credible-interval bounds of the Beta posterior. The absorption assumes $R_V = 3.1$ (Sect. 6.1).

The parallax-based distance is the mode of the hierarchical distance model applied to the Bailer-Jones et al. (2021) geometric distances of the members (Sect. 4.1); the distance from the distance modulus is obtained by converting the isochrone-fit distance-modulus marginal (Sect. 6.1), and is not independent of the parallax-based value because the distance-modulus prior was centered on it.

The values of R_c , k , and b are from the King fit to the 40 arcmin reference sample; R_t is from the 70 arcmin-window refit (Appendix D), the only extraction whose profile reaches a fitted background annulus beyond the cluster, with all narrower windows giving consistent R_t values. Finally, C combines the adopted R_c and R_t posteriors, which come from these two different fits.

3.2. Membership determination

To identify potential members of NGC 6383, we employed the HDBSCAN algorithm (Campello et al. 2013; McInnes et al. 2017), which identifies clusters of arbitrary shape and density

⁶ <https://scikit-learn.org>

⁷ <https://asteca.github.io>

⁸ <https://github.com/hutchresearch/Sagitta>

without a predetermined cluster number and is robust against noise and outliers (Hunt & Reffert 2021). After narrowing the data to a final subset of 15276 sources, HDBSCAN was applied only in the 2D proper-motion plane ($\mu_{\alpha^*}, \mu_{\delta}$). Parallax, angular position, and photometry were not used as clustering coordinates; they were used only in the filtering and subsequent characterization steps described below. The clustering used the Euclidean metric in proper-motion space. We also tested the [Haversine-haversine](#) metric, but it produced nonphysical groupings for this dataset.

To refine our selection of hyperparameters for optimal cluster identification, we tested the grid $m_{cl} = 10, \dots, 299$, setting $\text{min_cluster_size} = \text{min_samples} = m_{cl}$ in each run, then inspected both the number of recovered sources and the stability of the selected cluster. The HDBSCAN condensed tree is parameterized by the density level, $\lambda = 1/d_{\text{mreach}}$, where d_{mreach} is the mutual-reachability distance, so that larger λ corresponds to denser regions of the proper-motion plane. This parameter enters the analysis in three specific, limited ways; it is never a fitted physical parameter of the cluster. First, within each sweep run the NGC 6383 candidate branch is identified as the condensed-tree branch that contains the highest density level, λ_{max} , of the run, that is, the densest proper-motion over-density. Second, λ defines the per-source membership strength, $p_{\text{HDBSCAN},i}$, which enters the pseudo-probability defined below. Third, λ_{max} serves as a stability diagnostic of the hyperparameter sweep: the adopted min_cluster_size is the value that maximizes the size of the recovered branch, with λ_{max} acting only as a tie-breaker, and the sweep diagnostic in Appendix B displays only the stable regime, with $\lambda_{\text{max}} \geq 8$ and a recovered branch of 200–701 sources. This display cut affects neither the adopted configuration nor the membership.

We adopted $\text{min_cluster_size} = 43$, $\text{min_samples} = 43$, and the leaf cluster-selection method. These settings maximize the recovered NGC 6383 branch, while preserving a high separation from the field population in the condensed tree. The variation in cluster size as a function of the minimum cluster size is included with the HDBSCAN diagnostics in Appendix B. Because a single HDBSCAN run can overstate the significance of dense fluctuations in noisy data (Hunt & Reffert 2021), we derived a membership pseudo-probability that combines two factors obtained from the same $m_{cl} = 10, \dots, 299$ sweep. The first factor is the recovery frequency, f_i , defined as the fraction of the 290 sweep runs in which source, i , is assigned to a cluster rather than classified as noise; it measures the robustness of the assignment against the choice of m_{cl} . The second factor is the cluster-membership strength, $p_{\text{HDBSCAN},i}$, reported by HDBSCAN for the adopted configuration ($m_{cl} = 43$). HDBSCAN computes it from the condensed tree as $p_{\text{HDBSCAN},i} = \lambda_i / \lambda_{\text{max}}$, where λ_i is the density level at which source, i , leaves its cluster and λ_{max} is the highest density level attained within that cluster (McInnes et al. 2017). This strength equals 1 for sources that persist to the densest core of the over-density, decreases toward 0 for sources at the cluster boundary, and is 0 for noise. The membership pseudo-probability is the product $\tilde{p}_i = f_i p_{\text{HDBSCAN},i}$, so that a high value requires a source to be both stably recovered across the sweep and located close to the density core of the adopted clustering. This quantity is an operational ranking statistic and not a calibrated posterior membership probability. Sources of the selected NGC 6383 branch with $\tilde{p} > 0.5$ were retained as likely cluster candidates. The reference sample used for most cluster parameters adopts $\tilde{p} \geq 0.6$; sources with $0.6 \leq \tilde{p} < 0.8$ are referred to as probable members, while sources with $\tilde{p} \geq 0.8$ are referred to as members. These tiers are a priori round-number




Fig. 1. Membership pseudo-probability, $\tilde{p}$, of potential NGC 6383 members ($\tilde{p} > 0.5$) against their G magnitudes; each point is a star, color-coded by astrometric fidelity. The horizontal dashed and dotted lines, at $\tilde{p} = 0.6$ and $\tilde{p} = 0.8$, respectively, mark the thresholds used to distinguish between probable members ($0.6 \leq \tilde{p} < 0.8$) and members ($\tilde{p} \geq 0.8$) of the cluster.

conventions rather than tuned values; the stability of the mass-segregation result against the binary-classification threshold is verified in Sect. 7, and the stability of the membership itself is verified through the sweep-marginalized pseudo-probabilities.

Finally, we used the Astropy sigma-clipping (Astropy Collaboration et al. 2013, 2018, 2022) utility to apply a 2σ outlier rejection around the mode of the parallax distribution, a conventional rejection level chosen a priori. This step provided the sample of likely cluster candidates from which the $\tilde{p} \geq 0.6$ reference sample used for the cluster characterization was drawn.

The 40 arcmin run defines the production catalog used throughout this paper. To test whether the membership recovery was limited by this original search field, we repeated the complete preprocessing, HDBSCAN sweep, pseudo-probability calculation, and parallax clipping using input radii of 50, 60, and 70 arcmin. The adopted cluster parameters remain tied to the 40 arcmin reference catalog, except the King outer radius, which is measured on the widest extraction (Sect. 5); the setup and source counts of the robustness runs are reported in Sect. 3.3.

3.3. Membership of NGC 6383

Applying the HDBSCAN algorithm in the proper-motion plane returned several clusters. Given HDBSCAN’s tendency to report dense random fluctuations as clusters (Sect. 3.2), we selected the branch that is both stable in the condensed cluster tree and centered on the known proper-motion over-density of NGC 6383, which stands out as a compact, isolated clump in the proper-motion plane while overlapping the field on the sky (Fig. B.3, Appendix B). This cluster initially contained 701 sources, and after applying the 2σ parallax clipping described in Sect. 3.2, 321 sources were retained.

Regarding membership pseudo-probabilities (Fig. 1), NGC 6383 has 321, 254, 202, and 161 candidate members with $\tilde{p}$ above 50, 60, 70, and 80%, respectively. Correspondingly, 288,

236, 191, and 153 of these candidates are brighter than $G = 19$ mag. Table 2 shows a five-row excerpt of the likely-member catalog; the complete 321-source catalog is available at the CDS (see [Data-the section on data availability](#)), with the full column set listed in the table note and the CDS ReadMe.

The cone-search robustness experiment (Appendix D, Table D.1) shows how this selection behaves when the input field is widened; the corresponding astrometric and King-structural parameters recovered at each radius are compiled in Table D.2. The NGC 6383-like proper-motion branch is recovered in every run, but the recovered reference sample is not invariant with radius. In the 40 and 50 arcmin runs the generic sweep-selected branch coincides with the NGC-like branch. In the 60 and 70 arcmin runs, however, the generic branch selected by the sweep differs from the branch closest to the NGC 6383 proper-motion over-density, showing that the automated branch selection becomes field-window dependent in larger cones.

At the catalog level the solution is stable: the 50 arcmin run, in which the automated sweep selects the same branch as the NGC-like criterion, returns mean parallax, mean proper motions, and refitted King parameters consistent with the adopted values (Table D.2). At 60 and 70 arcmin, where the sweep-selected branch diverges from the NGC-like branch and the $\bar{p} \geq 0.6$ sample inflates to 443 and 628 sources, the solution degrades coherently: the proper-motion dispersions grow and the means drift (Table D.2), and the refitted profile reflects the added contamination through a smaller R_c , while the outer radius, now background-constrained, reaches 54_{-11}^{+7} arcmin (Sect. 5, Appendix D).

At the source level, the runs agree well: the wider fields recover 203 (80%), 242 (95%), and 252 (99%) of the adopted 254 at 50, 60, and 70 arcmin, and 192 sources (76%) appear in all four runs. The 50 arcmin run adds only 33 sources, all but one beyond the 40 arcmin footprint. The 60 and 70 arcmin runs, by contrast, add 201 and 376 sources, of which 83 and 114 lie inside the 40 arcmin footprint, the signature of a lowered effective selection threshold rather than of newly resolved outer structures. This behavior is consistent with increasing field contamination, although distinguishing contaminants from genuinely extended populations would require additional photometric, dynamical, or 3D diagnostics (Sect. 5). We therefore used the 40 arcmin catalog as the reference membership sample, and the wider extractions to constrain the outer structure (Sect. 5), while treating the outer membership and any quantity tied to the cluster boundary as search-window sensitive.

4. Astrometric parameters

With the membership fixed, we derive the cluster’s bulk kinematics and its position on the sky. Three of these quantities are used later: the distance converts angular to physical scales, the mean proper motion is the reference for the wider-field runs of Appendix D, and the center is the origin of the radial profile of Sect. 5.

4.1. Parallax and distance

Distance estimation from parallax is challenging due to measurement errors, making the conversion from parallax to distance via the simple inverse method unreliable (Bailer-Jones 2015; Bailer-Jones et al. 2021). Choosing an appropriate prior distribution is crucial. To address this challenge, we obtained photogeometric and geometric distances from Bailer-Jones et al. (2021),

who introduced a Bayesian approach incorporating a prior distribution tailored to different regions of the sky, improving distance estimates from *Gaia* EDR3 data. However, we opted not to use photogeometric distances due to the presence of PMS stars and gas in the cluster, which could distort the magnitudes and colors.

When analyzing the parallax measurements of stars within an open cluster and assuming a simplified 1D perspective, we assumed that the parallax values follow a normal distribution, $\varpi_i \sim \mathcal{N}(\mu_\varpi, \sigma_\varpi)$, where $\mathcal{N}(\mu, \sigma)$ denotes a normal distribution with mean, μ , and standard deviation, σ . The mean was given a uniform prior, $\mu_\varpi \sim \mathcal{U}(0.5 \bar{\varpi}, 1.5 \bar{\varpi})$, where $\mathcal{U}(a, b)$ denotes the uniform distribution on the interval $[a, b]$ and $\bar{\varpi}$ is the arithmetic mean of the observed parallaxes of the sources entering the fit (those with fractional parallax error below 0.1; see below). The dispersion was given a half-normal prior, $\sigma_\varpi \sim \mathcal{HN}(s_\varpi)$, where $\mathcal{HN}(s)$ denotes the half-normal distribution with scale, s , and s_ϖ is the standard deviation of the same observed parallaxes. We use the $\mathcal{N}$, $\mathcal{U}$, and $\mathcal{HN}$ notation for all priors in the remainder of the paper. Additionally, we assumed a gamma distribution for the distances, parameterized by its mean, μ_r , and width, σ_r , the latter with a half-normal prior, $\sigma_r \sim \mathcal{HN}(s_r)$, with s_r the standard deviation of the geometric distances introduced above. This data-dependent scale is the one used for the fits reported here, obtained with the code as of 2026 July 19; the currently released package instead adopts a fixed scale of 0.05 kpc, set from the Hunt & Reffert (2024) cluster census rather than from the sample being fitted. Re-running the fit with the fixed scale moves neither of the two numbers quoted below: the mode sampled distance changes by 3×10^{-4} kpc and σ_r by 6×10^{-5} kpc. More generally, varying that scale over 0.025–0.20 kpc, an eightfold range that brackets both choices, changes the recovered σ_r by 0.0013 kpc (2% of its value, and 0.7% of the range swept) and leaves the mode sampled distance within 3×10^{-4} kpc; repeating one fit with four different sampler seeds moves σ_r by 8×10^{-5} kpc, so that 0.0013 kpc is a response to the prior and not sampling noise. The line-of-sight depth we report is therefore set by the data rather than by its prior. This holds in the regime sampled here, where the depth is comparable to the individual distance uncertainties; for a cluster whose depth is far smaller than those uncertainties the likelihood flattens near zero and the same scale contributes a substantially larger share of the reported width. These checks are reproduced by `tools/probes/distance_prior_sensitivity.py` in the repository cited above.

In our hierarchical model, we calculated the mean (μ_{prior}) between the frequentist average distance derived from parallaxes and the Bailer-Jones et al. (2021) geometric distances, using $\mathcal{U}(0.5\mu_{\text{prior}}, 1.5\mu_{\text{prior}})$ as the prior for the cluster’s mean distance. Our analysis is limited to sources with a fractional parallax error below 0.1; namely, $\delta\varpi/\varpi < 0.1$, where $\delta\varpi$ is the *Gaia* parallax uncertainty, to ensure accuracy.

The mean parallax of the subsample used for the distance estimate is 0.908 mas, with a 1σ dispersion of 0.046 mas and a standard error on the mean of 0.004 mas (Fig. 2). The mode sampled distance is 1.11 ± 0.06 kpc. These values slightly deviate from the results obtained in earlier studies (Trumpler 1930; Sanford 1949; Fitzgerald et al. 1978; The et al. 1985; Paunzen et al. 2007) but agree with Becker & Fenkart (1971) and with later determinations (Kharchenko et al. 2005; Piskunov et al. 2008; Jaehnig et al. 2021; He et al. 2022; Pulgar-Escobar & Henríquez-Salgado 2024; Hunt & Reffert 2024).

Table 2. Excerpt of the likely-member catalog for NGC 6383.

GaiaDR3	RAdeg (deg)	DEdeg (deg)	Gmag (mag)	pHDBSCAN	pFreq	pMember	Ref
4053793547964747904	264.16939344	-33.03325935	17.9052	0.7959	0.9793	0.7795	1
4054500465190725632	263.10710918	-32.96962071	20.1954	0.6985	0.9793	0.6840	1
4054501599068361216	263.08486813	-32.91805440	15.1189	0.8585	0.9793	0.8407	1
4054514449600386304	263.64147648	-33.22555846	16.3805	0.9110	0.9828	0.8953	1
4054518023012382592	264.01601176	-33.15455344	14.6423	0.6760	0.9793	0.6620	1

Notes. The complete machine-readable table is available at the CDS and contains the following columns: GaiaDR3, RAdeg, DEdeg, Plx, e_Plx, pmRA, e_pmRA, pmDE, e_pmDE, Gmag, BPmag, RPmag, Jmag, Hmag, Ksmag, Fidelity, pHDBSCAN, pFreq, pMember, Ref, PMSProb, AvSag, and logAgeSag. Here, pMember is the composite membership pseudo-probability, $\tilde{p} = p_{\text{HDBSCAN}} f_i$. The column Ref is equal to one for sources belonging to the $\tilde{p} \geq 0.6$ reference sample used for the main cluster parameters, and zero otherwise.




Fig. 2. *Left panel:* Parallax distribution of the 254-source reference sample, split by fractional parallax error into the subsample used for the estimate ($\delta w/w < 0.1$), all sources, and the discarded $\delta w/w > 0.1$ sources; the smooth curve is a Gaussian fit, and the dash-dotted line and shaded band mark the mean parallax and its standard error. *Middle panel:* G magnitude versus parallax with the same split; horizontal bars are the individual parallax uncertainties and the shaded band the 1σ parallax dispersion. *Right panel:* Bailer-Jones geometric distances (Bailer-Jones et al. 2021) with the same split; the dash-dotted line and shaded band mark the adopted distance (the mode of the sampled distances) and its dispersion. Values are given in the panel legends. For convenience, only the portion of the histogram corresponding to distances within 0.8 to 1.2 times the minimum and maximum used distances is displayed.

4.2. Proper motions and radial velocities

We used a 2D Gaussian to model the distribution of the proper motions of the cluster members. A normal prior distribution was assigned to the mean proper motions, $[\bar{\mu}_\alpha, \bar{\mu}_\delta]$, based on frequentist means and standard deviations. For the standard deviations, we used half-normal priors with a width equal to the frequentist standard deviation of the proper motions, and the correlation coefficient between the proper motions was uniformly distributed over the interval $[-1, 1]$. Additionally, we estimated the mean total proper motion of the cluster, defined as the quadrature sum of the proper-motion components.

The mean proper-motion values are $2.542 \text{ mas yr}^{-1}$ in R.A. and $-1.713 \text{ mas yr}^{-1}$ in Dec., with member dispersions of 0.152 and $0.138 \text{ mas yr}^{-1}$, respectively, which align with the acceptable values from Perren et al. (2023) (Fig. 3). The corresponding standard errors on the means are 0.0096 and $0.0086 \text{ mas yr}^{-1}$, but these smaller values are not used as the physical width of the cluster when comparing individual stars. The posterior distribution of the total proper motion, derived as the quadrature sum of the two components in each draw, has a median of $3.065 \pm 0.009 \text{ mas yr}^{-1}$, corresponding to a projected (tangential) velocity of $16.1 \pm 0.9 \text{ km s}^{-1}$ at the adopted distance.

The dispersions quoted above are those of the observed member sample and therefore still contain the *Gaia* measure-

ment scatter. Because the per-source proper-motion uncertainties of the members span two orders of magnitude (median 0.104 and $0.074 \text{ mas yr}^{-1}$ in $\mu_{\alpha*}$ and μ_δ , with 32% and 23% of members having uncertainties larger than the observed scatter itself), subtracting a mean error in quadrature is not defined here: it returns a negative variance in both axes. We therefore estimated the intrinsic dispersion by maximum likelihood, modeling each member as $\mu_i \sim \mathcal{N}(\bar{\mu}, \sigma_{\text{int}}^2 + e_i^2)$, with its own uncertainty e_i , which gives $\sigma_{\text{int}} = 0.122$ and $0.121 \text{ mas yr}^{-1}$ in $\mu_{\alpha*}$ and μ_δ , that is a 1D intrinsic dispersion of $0.122 \text{ mas yr}^{-1}$, or 0.64 km s^{-1} at the adopted distance. The apparent excess of the R.A. over the Dec. dispersion (a ratio of 1.11 in the observed values) disappears after this deconvolution (a ratio of 1.00), showing it to be an artifact of the *Gaia* error budget, which is larger in $\mu_{\alpha*}$, rather than a kinematic anisotropy. The intrinsic value is more sensitive to the membership selection than to the fit: repeating the estimate at $\tilde{p} \geq 0.5, 0.7$, and 0.8 gives $0.150, 0.102$, and $0.089 \text{ mas yr}^{-1}$, a monotonic trend that reflects the progressive truncation of the member sample in proper-motion space rather than a symmetric uncertainty, so we treat this quantity as selection-limited. We retained the observed dispersions in Table 1 and in the individual star comparisons below because they are the appropriate width against which we can consider whether a single star is an outlier of the observed member population. We quote the intrinsic value here only for comparison with dynamical work.




Fig. 3. Proper motions of the likely cluster candidates ($\bar{p} > 0.5$) of NGC 6383; the symbols are color-coded according to the membership pseudo-probability, $\bar{p}$, of the stars. The gray solid ellipses are the 1σ , 2σ , and 3σ iso-probability contours of the 2D Gaussian proper-motion model fitted to the reference sample. The inferred mean proper motion is marked with a blue cross and with the orange dashed lines through it.

Gaia DR3 radial velocities are available for only 11.4% of the reference sample (29 of 254 sources). Because sources with large radial-velocity amplitudes, likely unresolved binaries, can bias the cluster’s radial-velocity estimate, we restricted it to the 16 clustered sources with $\bar{p} \geq 0.6$ and a binary probability (an ASteCA product; Sect. 7) lower than 0.6. The resulting median, mean, and standard deviation are -1.87 , -9.40 , and 32.1 km s^{-1} , respectively. The substantial standard deviation primarily stems from the limited availability of radial velocity data, and even with the binary cut the small sample makes this only an indicative measure of the cluster’s internal dynamics. Figure C.6 illustrates all the probable members and members with available radial velocities, their magnitudes, and the amplitude of their radial velocities.

4.3. Cluster center

To determine the cluster’s center, we used a weighted kernel density estimation (KDE) from the Python library *scikit-learn* (Pedregosa et al. 2011), assigning weights inversely proportional to the distance from the mean proper motion. Optimal KDE parameters were determined through a grid search cross-validation within the package, exploring a range of bandwidths (from the mean positional error to the cone-search radius) and all kernel types; the selected bandwidth ($\approx 6.7 \text{ arcmin}$) dominates the quoted center uncertainty. The location of maximum density was taken as the cluster’s center.

The central position of the cluster in equatorial coordinates is $263.683 \pm 0.112^\circ$ in R.A. and $-32.584 \pm 0.112^\circ$ in Dec. (Fig. 4). These errors are calculated from the quadratic sum of the mean errors in R.A. and Dec., and the optimal KDE bandwidth. This center is consistent, within the quoted uncertainty, with the projected coordinates of HD 159176; the positional coincidence is therefore not sufficient by itself to establish membership.




Fig. 4. Spatial distribution of the likely cluster candidates ($\bar{p} > 0.5$) of NGC 6383 in right ascension (α) and declination (δ), color-coded according to their membership pseudo-probability, $\bar{p}$. The gray solid contours are the 1σ and 2σ iso-density contours (enclosing 39% and 86% of a kernel density estimate of the candidate positions, revealing the density gradient of the points). The central coordinates of the cluster are marked by dark-orange dashed lines, which approximately coincide with the density peak within the plotted area.

5. Cluster structure

To determine the structural parameters of the cluster, we utilized the King (1962) density profile. The numerical density, ρ , was computed by dividing the cluster area into concentric annuli, each containing an equal number of stars. The number of annuli, K , adheres to the equiprobable bin rule ($K = 2n^{2/5}$), where n is the star count within the cluster. The annular densities were fit with a Gaussian likelihood whose scatter is a half-normal nuisance parameter, yielding the posterior distribution of the structural parameters.

Priors for the model parameters were set as follows: $b \sim \mathcal{U}(0, 2\rho_{\min})$, $k \sim \mathcal{U}(b, 2\rho_{\max})$, $R_c \sim \mathcal{U}(0, 0.8 T_{\max})$, and $R_t \sim \mathcal{U}(R_c, 1.5 T_{\max})$, where b is the background density, k the central normalization, $\rho_{\min}$ and $\rho_{\max}$ the observed surface-density extrema, and $T_{\max}$ the highest value between the Hill radius and the gravitational bound radius, both defined below. These coefficients are not tuned values but weakly informative bounds anchored to the largest physically meaningful scale of the system. The upper limit on R_c lies more than an order of magnitude above any realistic open-cluster core radius. The upper limit on R_t allows the fitted outer radius to exceed the nominal gravitational bound radius by up to 50%, offering generous headroom for the uncertainties in the cluster mass and Galactic potential that enter $T_{\max}$.

The posterior of R_c is well-confined-lies well inside its support (97.5th percentile at $\approx 2.5 \text{ arcmin}$, 7% of the prior upper bound), so its bound is immaterial. Refitting the 40 arcmin profile with alternative coefficients (e.g., $0.9 T_{\max}$ and $1.2 T_{\max}$) changes R_c , k , b , and C by less than 0.5σ ; only the weakly constrained outer radius responds (median $R_t \approx 33 \text{ arcmin}$ versus $40^{+16}_{-17} \text{ arcmin}$, consistent within 1σ). For the adopted 70 arcmin fit the same coefficients act differently, and the arithmetic is worth stating: with $T_{\max} = 42.5 \text{ arcmin}$, a bound of $1.2 T_{\max} = 51.0 \text{ arcmin}$ lies below the adopted $R_t = 54 \text{ arcmin}$, so any coeffi-

cient smaller than 1.27 excludes the adopted value from the prior support outright rather than perturbing it. This is not an independent objection to that value but the same prior limitation seen from the opposite side: R_t is bounded from above by the prior in every window we fit, which is why we report it as conditional on the bound and quantify the relaxed case below. The outer radius is the one parameter whose posterior is sensitive to the prior support in all windows: the upper bound $1.5 T_{\max} = 63.7$ arcmin truncates the R_t posterior of every fit. All quoted R_t intervals are therefore conditional on this physically motivated prior (Appendix D), reinforcing its interpretation as a model-dependent outer scale.

The Hill radius (R_{Hill}) defines the region around a star cluster where its gravitational influence dominates over that of the Galaxy. It can be calculated following Carrera et al. (2019), expressed as

$$R_{\text{Hill}} = R_{\text{gc}} \times \left(\frac{m_c}{3M_{\text{gc}}} \right)^{1/3}, \quad (1)$$

where $R_{\text{gc}} = (R_{\odot}^2 + d^2 - 2R_{\odot}d \cos l \cos b)^{1/2} = 7.19 \pm 0.06$ kpc is the galactocentric distance of the cluster, computed from its Galactic coordinates (l, b), the parallax-based distance $d = 1.11 \pm 0.06$ kpc, and a solar galactocentric radius $R_{\odot} = 8.3$ kpc (de Grijs & Bono 2016), with the uncertainty propagated from the distance and cluster-center uncertainties, m_c the cluster mass from Hunt & Reffert (2024), with a value of $902 \pm 92 M_{\odot}$, and M_{gc} the Galactic mass enclosed within the cluster's orbit, estimated from the circular velocity of the McMillan (2017) Galactic potential at R_{gc} , $V_c(7.19 \text{ kpc}) \approx 229 \text{ km s}^{-1}$, as

$$M_{\text{gc}} = \frac{V_c^2(R_{\text{gc}}) R_{\text{gc}}}{G} = (8.8 \pm 0.5) \times 10^{10} M_{\odot}. \quad (2)$$

Moreover, the gravitationally bound radius was estimated using the method described by Pinfield et al. (1998), which considers the cluster mass and Oort constants, using the formula

$$r_{\text{bound}} = \left(\frac{Gm_c}{2(A - B)^2} \right)^{1/3}, \quad (3)$$

where G is the gravitational constant, and A and B are the Oort constants, with values from Bovy (2017).

The King fit to the 40 arcmin reference sample yields a core radius, $R_c = 1.96^{+0.19}_{-0.16}$ arcmin ($0.63^{+0.06}_{-0.05}$ pc), with $k = 4.92^{+0.43}_{-0.31}$ and background $b = 0.011 \pm 0.007$ stars per square arcminute (Fig. 5). The outer radius, however, is not usefully constrained by this window: the fit returns $R_t = 40^{+16}_{-17}$ arcmin with half of the posterior mass beyond the extraction radius itself, because the field contains almost no background annulus beyond the cluster.

We therefore measure the outer structure on the wider extractions of Appendix D, refitted with identical priors. The fitted R_t is mutually consistent across all windows (Table D.2), and the 70 arcmin window is the only one whose radial profile reaches a fitted background annulus beyond the cluster (Fig. D.1). We adopted $R_t = 54^{+7}_{-11}$ arcmin ($17.4^{+2.3}_{-3.6}$ pc) as the King outer radius. This interval remains conditional on the $R_t < 1.5 T_{\max} = 63.7$ arcmin prior: relaxing the bound to the extraction edge ($R_t < 70$ arcmin) shifts the posterior to 58^{+9}_{-13} arcmin, consistent within 1σ , with the upper tail still limited by the prior support rather than turned over by the data. The wider windows also admit additional field contamination in the membership (Sect. 3.3), which lowers the fitted R_c to ≈ 1.4 arcmin at 60–70 arcmin; the selection-stable 50 arcmin run returns $R_c = 1.90^{+0.15}_{-0.13}$ arcmin,




Fig. 5. Radial density profile of NGC 6383 in logarithmic scale: annular number densities of the reference sample with the King model at the posterior median and its 16–84% posterior band. The vertical lines mark the core radius and the outer radius preferred by this 40 arcmin-window fit, and the horizontal line the fitted background level b . The adopted outer radius, $R_t = 54^{+7}_{-11}$ arcmin, is measured on the 70 arcmin extraction (Appendix D, Fig. D.1).

confirming the adopted core radius. Combining the adopted R_c and R_t posteriors gives a concentration parameter of $C = \log_{10}(R_t/R_c) = 1.43^{+0.07}_{-0.10}$ (Peterson & King 1975). Because the added outer sources cannot be separated from field contamination without additional diagnostics (Risbud et al. 2025; Xu et al. 2025), R_t remains a model-dependent scale rather than a sharp physical boundary. All the radii quoted here come from a circularly symmetric fit; no axis ratio was fitted, so R_c should be read as the geometric-mean scale radius of the projected distribution rather than as a semi-major axis. The half-light radius is determined to be 6.02 ± 1.07 arcmin (1.94 ± 0.36 pc, bootstrap uncertainty) and the half-mass radius is 6.26 ± 1.23 arcmin (2.02 ± 0.41 pc).

Measuring the outer structure on a field substantially larger than the cluster itself follows established *Gaia* DR3 practice (Angelo et al. 2025); even so, the wider-field tests (Appendix D, Table D.1) show that the number of outer candidates changes with the input field, so we do not classify the larger-radius additions as confirmed halo members or contaminants. We identify 18 sources beyond the Hill radius (33.6 arcmin) with cluster-like proper motions (pseudo-probabilities 0.64–1.0, mean 0.81; Fig. C.3); all lie within the 40 arcmin extraction, and hence well inside the adopted R_t . They also lie inside the gravitational bound radius (42.5 arcmin); we nevertheless flag them because the Hill radius, which accounts for the Galactic tidal field at the cluster's orbit, is the more conservative boundary of guaranteed boundness, so their membership in the bound system is not certain.

6. Age, extinction, and stellar content

With the membership and the spatial structure fixed, we turn to the photometry. Two routes are followed independently: an isochrone fit to the cluster as a whole, returning age, metallicity, extinction, and distance modulus (Sect. 6.1), and a per-star neural-network classification of the PMS population with indi-

vidual ages and extinctions (Sect. 6.2). Their assumptions differ, so the two are compared rather than combined.

6.1. Isochrone fitting with ASteCA

ASteCA (Perren et al. 2015) is an open-source Python tool designed to automate standard tests for determining basic parameters of stellar clusters. For accurate estimation of a cluster’s metallicity, age, and extinction values, we employed ASteCA’s isochrone fitting process. We utilized the MESA Isochrones and Stellar Tracks (MIST) isochrones (Dotter 2016; Choi et al. 2016) along with the photometric systems of *Gaia* EDR3 and 2MASS. The initial mass function followed Chabrier et al. (2014). Synthetic binaries were generated with the mass-dependent binary fraction adopted in ASteCA, $b(m) = \alpha + \beta/(1 + 1.4/m)$ with $\alpha = 0.090$ and $\beta = 0.940$ held fixed; this parameterization is ASteCA’s analytic fit to the observed multiplicity fraction as a function of primary mass compiled by Offner et al. (2023), and with these coefficients it reproduces the observed binarity across spectral types, rising from ≈ 0.26 for M dwarfs through ≈ 0.5 for solar-type stars to $\gtrsim 0.9$ for O-type stars (Duchêne & Kraus 2013; Moe & Di Stefano 2017). Secondary masses were drawn from the mass-ratio distribution, $f(q) \propto q^\gamma$ with the mass-dependent exponents of Duchêne & Kraus (2013); differential reddening was fixed to zero.

The MIST ages inherit the physical assumptions of the underlying models: we used the v1.2 grids, which adopt solar-scaled abundances on the Asplund et al. (2009) scale ($Z_\odot \approx 0.0142$), a single solar-calibrated mixing-length parameter ($\alpha_{\text{MLT}} = 1.82$), exponentially decaying convective overshooting ($f_{\text{ov,core}} = 0.016$, $f_{\text{ov,env}} = 0.0174$), and an initial rotation of $v/v_{\text{crit}} = 0.4$ imposed at the zero-age main sequence, so the PMS tracks that dominate our fit are effectively non-rotating. The models include neither magnetic inhibition of convection, nor starspots, nor an accretion history; magnetic and spotted PMS models yield systematically older ages for young clusters, by a factor of ~ 2 or more (Feiden 2016; Somers & Pinsonneault 2015), with the SPOTS grids showing the same systematic (Somers et al. 2020), so the absolute PMS age scale is tied to these assumptions.

The priors for metallicity Z , logarithmic age, and absorption A_V were defined as uniform distributions ranging from $[0.001, 0.045]$, $[6.00, 7.00]$, and $[0.5, 2]$, respectively, aligned with the findings of Pulgar-Escobar & Henríquez-Salgado (2024). The distance modulus was modeled as $\mathcal{N}(10.3, 0.2)$, with the mean value corresponding to the expected distance modulus obtained from the parallax. We used only the MIST PMS evolutionary models for the present fit; the fitted spread therefore describes the uncertainty within this model family alone, and the systematic differences that arise from alternative PMS tracks are added separately when the adopted age interval is quoted below. We adopted the mode of the fitted distribution for our analysis and sampled the model with the gradient-free DEMetropolis ensemble sampler (Sect. 3.1) instead of the ~~Approximate-Bayesian Computation~~ ~~approximate Bayesian computation~~ (ABC) suggested by ASteCA. The nuisance parameter, σ_z shown in the corner plot (Fig. B.4) is the likelihood-scatter term of the fit; it is not a physical velocity, spatial, or age dispersion of the cluster.

To determine the cluster’s age, extinction, and metallicity, we fit MIST isochrones to the color-magnitude diagram (CMD) of NGC 6383 (Fig. 6, which shows the PMS stars and the mode, mean, and median isochrones). The mode indicates a logarithmic age in years of 6.55, a distance modulus of 10.30 ± 0.09 mag corresponding to a distance of 1.15 ± 0.05 kpc, and a metallicity,

$Z_\odot$ of 0.024 ± 0.008 , slightly above the MIST solar value ($Z_\odot \approx 0.0142$); we note that the absolute metallicity is only loosely constrained by the isochrone fit because of the age–metallicity–extinction degeneracy, and the value lies within the adopted prior. An estimated extinction correction of $A_V = 1.24 \pm 0.26$ was applied, with the total-to-selective extinction ratio fixed at $R_V = 3.1$ and the Cardelli et al. (1989) extinction law with the optical coefficients of O’Donnell (1994), as implemented in ASteCA. A normal extinction law is supported within the cluster itself: van den Ancker et al. (2000) found no deviation from $R_V = 3.1$ in any of the 13 core stars for which they determined it. The corresponding color excess, $E(B - V) = A_V/R_V = 0.40 \pm 0.08$ mag (the $\pm$ inheriting the ensemble spread of A_V ; Table 1), lies within the 0.26–0.51 mag range of the literature determinations compiled in Table A.1: above most of those published up to 2019 (0.26–0.35 mag), consistent with the 0.39–0.47 mag of the three most recent (He et al. 2022; Hunt & Reffert 2024; Pulgar-Escobar & Henríquez-Salgado 2024), and below the 0.51 ± 0.03 mag of Aidelman et al. (2018). This CMD-derived distance is consistent with the parallax-based value of 1.11 ± 0.06 kpc (Table 1), as expected given that the distance-modulus prior was centered on it, and we adopted the parallax value for all structural-radius conversions.

We caution that the age is a weakly constrained quantity and that the width of its posterior is not a measure of the precision of the fit: the marginal retains a substantial fraction of the adopted $\mathcal{U}(6.00, 7.00)$ prior width, so its standard deviation (0.15 dex) is a lower bound on the true uncertainty rather than a statistical error, and we do not quote it as one. The realistic uncertainty toward older ages is set by the PMS model family: starspots shift isochrone-derived PMS ages by factors of 2–10 at 3 Myr (Somers & Pinsonneault 2015), and magnetic inhibition of convection by a factor of ~ 2 for the K and M stars of the ~ 10 Myr Upper Scorpius association (Feiden 2016), that is by 0.3–1.0 dex, and neither is included in the MIST v1.2 grids used here (see above). The other age indicators available for this cluster do not constrain it independently. The median Sagitta age of the 116 PMS candidates of the same membership, $\log(\text{age}) = 6.75$ (Sect. 6.2), is 0.2 dex above the fitted mode, comparable to the 0.14 dex offset between the Sagitta and MIST age scales measured in the Orion Complex by Kounkel et al. (2023); the isochrones that enclose the bulk of the observed PMS locus, $\log(\text{age}) = 6.20$ – 6.80 (Fig. 7), come from the same model grid and the same data as the fit. We therefore adopted $\log(\text{age yr}^{-1}) = 6.55^{+0.40}_{-0.20}$, i.e., ≈ 3.5 Myr with a factor ≈ 2.5 of room toward older ages and ≈ 1.6 toward younger ones. The two bounds have different origins. The upper bound, +0.40 dex, is the conservative lower half of the range spanned by the PMS systematics quoted above, which push the age older. The lower bound is a judgment, not a measurement: as we have not identified an effect that would shift the age of the cluster as a whole younger, it only moderately widens the 0.15 dex marginal standard deviation (itself a lower bound), and the young side of the PMS locus cannot set it, because unresolved binaries, differential reddening, and accretion variability broaden that locus (see below).

The CMD, particularly for sources brighter than $G = 12.0$ mag, displays a well-defined main sequence. The presence of PMS stars and ~~lower-mass-lower-mass~~ main sequence stars broadens the lower part of the CMD, complicating the fit of a single isochrone. Figure 7 presents various isochrones for *Gaia* and 2MASS data, considering ages between 6.20 and 7.00 in logarithmic scale and initial metallicities, $Z_\odot$ of 0.024. The isochrones of $\log(\text{age}) = 6.20$ and 6.80 (about 1.6 and 6.3 Myr) enclose the




Fig. 6. CMD of NGC 6383 (G_{mag} versus $G_{\text{BP}} - G_{\text{RP}}$) with the Sagitta-based PMS classification: orange filled symbols are PMS candidates (Sagitta PMS probability ≥ 0.6), blue filled symbols are non-PMS sources, and open black symbols are sources without 2MASS photometry, which are left unclassified; stars denote members ($\bar{p} \geq 0.8$) and diamonds probable members ($0.6 \leq \bar{p} < 0.8$). The black solid, dashed, and dotted curves are the synthetic single-star sequences at the mode, mean, and median of the isochrone-fit ensemble, and the light-gray curves are 150 single-star sequences drawn from that ensemble.

bulk of the PMS locus: about 60% of the PMS candidates in the left panel lie between them and the rest on either side, a fraction that does not depend on how the isochrone color is matched at each magnitude, although the split between the two sides does. Older isochrones show the sensitivity of the fit. Because unresolved binaries, differential reddening (fixed to zero in the fit), and accretion variability also broaden the locus (Da Rio et al. 2010), this range is an upper limit on the age spread of the corresponding fraction of the true population.

Figure 7 also includes color-color diagrams ($G_{\text{BP}} - G_{\text{RP}}$) showing a clearer segregation of PMS stars, which tend to be at redder colors, as expected. The joint distribution of the inferred parameters is shown as a plot pair in Fig. B.4.

6.2. PMS content and YSO fraction

Sagitta is a neural network designed to classify stars as PMS and estimate their ages. It is trained with data from *Gaia* DR2 and 2MASS. It incorporates three convolutional neural networks each dedicated to determining stellar extinction (A_V), PMS probability, and estimating stellar ages. Sagitta’s age estimation is applicable for young stars up to ~ 80 Myr and relies on inputs including *Gaia* parallaxes, and average line-of-sight extinction (McBride et al. 2021).

No theoretical PMS evolutionary model enters Sagitta directly: it is trained on empirical age labels (McBride et al. 2021). Most are the mean ages of the *Gaia* moving groups of Kounkel et al. (2020), inferred with their Auriga neural network, whose training ages come from the PARSEC isochrones (Marigo et al. 2017) and, through the Milky Way

Star Clusters (MWSC) catalog (Kharchenko et al. 2013), from Padova isochrones with the Siess et al. (2000) PMS models. Because Auriga overestimates young ages, well-studied star-forming regions were relabeled with literature ages compiled by McBride et al. (2021), mostly from the *Handbook of Star Forming Regions*, which rest on heterogeneous PMS models. The Sagitta age scale is therefore that of no single grid, and in particular not the MIST v1.2 scale of Sect. 6.1. Its offsets against individual grids have been measured in the Orion Complex, itself part of the Sagitta training set: Sagitta ages are 0.14 and 0.17 dex older than MIST and PARSEC ages, respectively, and closest to those of Baraffe et al. (2015) (-0.05 dex) and of the SPOTS models (Somers et al. 2020) with 17% spot coverage ($+0.01$ dex); in a coevality test within the same groups, Sagitta ages also depend less on effective temperature than the ages from any of these grids, partly by construction (Kounkel et al. 2023). NGC 6383 is also one of the relabeled regions, with a training label of 2 Myr after Rauw & De Becker (2008); the median Sagitta age of our PMS candidates, $\log(\text{age}) = 6.75$, lies 0.45 dex above it, so these ages do not simply reproduce the label. Sagitta ages carry a characteristic uncertainty of ~ 0.3 dex, from the dispersion of the ages assigned to the same stars placed at different distances (McBride et al. 2021). Although the network was trained on *Gaia* DR2 photometry, we apply-applied it to the corresponding *Gaia* DR3 bands.

Identifying PMS stars and estimating their ages traces the cluster’s star-formation history. Sagitta is most reliable for PMS stars, as the photometry of higher-mass stars that have reached the main sequence is not indicative of their age, limiting the model’s applicability to stars that remain in the PMS stage.

Applying Sagitta to the membership yields 116 of the 254 reference-sample sources (133 of the 321 likely candidates) with a PMS probability of at least 0.6, the threshold used for the PMS class throughout this paper. The distributions of the per-star Sagitta PMS probabilities, ages, and extinctions are shown in Fig. C.4. These histograms are individual-star Sagitta estimates and should not be read as the same posterior summarized in Table 1: the broader Sagitta distributions, including the high-extinction tail and older age tail, reflect star-to-star extinction, photometric scatter, unresolved binaries, and the fact that Sagitta is applied to individual PMS candidates, whereas the ASteCA values in Table 1 are cluster-level isochrone-fit parameters.

Young stellar objects are early-stage stars still accreting material from circumstellar disks; they include protostars and the more evolved PMS stars, the latter comprising classical T-Tauri and Herbig Ae/Be stars.

Our analysis is aimed at quantifying the fraction of YSOs within the cluster, noted as Y_{frac} , which serves as an age indicator. We determined the reddening-free parameter, Q , for each star using

$$Q = (J - H) - \frac{E(J - H)}{E(H - K)}(H - K), \quad (4)$$

where $E(J - H)/E(H - K)$ is assumed to be 1.55 (Mathis 1990). Following Buckner & Froebrich (2013), a star is considered a YSO if its Q value is less than -0.050 mag.

We followed the method of Cameron (2011) to estimate Y_{frac} and its uncertainty. Using a non-informative $\mathcal{B}(1, 1)$ prior, where $\mathcal{B}(a, b)$ denotes the Beta distribution with shape parameters, a and b , the posterior distribution for Y_{frac} is modeled as

$$Y_{\text{frac}} = \frac{N_{\text{YSO}}}{N_{\text{cl}}}, \quad (5)$$




Fig. 7. *Left panel:* CMD of NGC 6383 showing G_{mag} against $G_{\text{BP}} - G_{\text{RP}}$ with isochrones for $\log(\text{age yr}^{-1})$ ranging from 6.20 to 7.00. *Middle panel:* CMD using G_{mag} versus $G_{\text{RP}} - J$. *Right panel:* Color-color diagram, $G_{\text{RP}} - J$ against $G_{\text{BP}} - G_{\text{RP}}$, with the equivalent color-color isochrones. Symbols as in Fig. 6. The MIST isochrones for $\log(\text{age}) = 6.2\text{--}7.0$ (at $Z_{\text{ini}} = 0.024$) are drawn with sequentially ordered colors and distinct line styles, identified in the left-panel legend.

where N_{YSO} is the number of YSOs and $N_{\text{cl}} = 193$ is the number of reference-sample sources with 2MASS JHK_s photometry, for which Q can be computed (out of the 254 sources in the reference sample). The 95% credible interval for Y_{frac} was then derived from the posterior Beta distribution.

We identified 53 YSOs, with a mean Q value of -0.528 , a median of -0.389 , and a standard deviation of 0.421 for sources below -0.050 mag.

The resulting Y_{frac} is 0.275 , with a 95% credible interval of $[0.217, 0.342]$. This value is conditional on 2MASS detectability: the 61 reference sources without 2MASS counterparts are systematically fainter (median $G = 18.1$ versus 16.6 ; Kolmogorov-Smirnov (KS) $p \sim 10^{-6}$), and the limiting assumptions that none or all of them are YSOs bound Y_{frac} to $[0.21, 0.45]$. The value is higher than those reported by Buckner & Froebrich (2013), who found only 18 of 397 cluster candidates with $Y_{\text{frac}} > 0.100$ and no cluster with $Y_{\text{frac}} > 0.200$; since the two samples are not selection-matched, we read this as an indicative, not quantitative, sign that NGC 6383 is younger or more active in recent star formation than most clusters in their study.

7. Luminosity, mass, and dynamical state

Having established the cluster’s membership, structure, and stellar content, we now examine its luminosity function, individual stellar masses, and dynamical state, all derived for the $\bar{p} \geq 0.6$ reference sample. For NGC 6383, we converted apparent G magnitudes to absolute magnitudes using the parallax-derived distance. Figure C.2 shows the luminosity function, indicating an increase toward dimmer magnitudes.

The radial cumulative distributions of cluster members at various magnitude levels, illustrated in Fig. 8, show that fainter stars, ranging from 17.93 to 20.66 mag, are less concentrated around the cluster’s center. This observation is consistent with *Gaia*’s completeness limit for magnitudes between 18 and 19 at distances around 1 kpc (Boubert & Everall 2020; Castro-Ginard et al. 2023). To test whether this reflects a real spatial difference, we compared the radial distribution of the




Fig. 8. Normalized cumulative counts of reference-sample stars ($\bar{p} \geq 0.6$) versus distance from the cluster center, in four G_{mag} quartiles (solid, dashed, dotted, and dash-dotted curves from brightest to faintest; ranges in the legend). The black dash-dotted and black dotted vertical lines mark the core radius, $R_c = 1.96$ arcmin, and the Hill radius, $R_{\text{Hill}} = 33.6$ arcmin; the adopted King outer radius, $R_t = 54^{+7}_{-11}$ arcmin (Appendix D), lies beyond the plotted range of this 40 arcmin sample.

faintest quartile with that of each of the three brighter quartiles using two-sample KS tests. The faintest quartile differs from the two intermediate quartiles ($G = 16.99\text{--}17.93$ mag: $D = 0.28$, $p = 0.010$; $G = 15.44\text{--}16.99$ mag: $D = 0.23$, $p = 0.052$), but is statistically indistinguishable from the brightest quartile ($G = 8.80\text{--}15.44$ mag: $D = 0.16$, $p = 0.42$); after a Holm correction for the three tests, only the difference with respect to the $16.99\text{--}17.93$ mag quartile remains significant. If the lower cen-

tral concentration of the faintest stars were caused by dynamical mass segregation, the contrast should be strongest with respect to the brightest (most massive) quartile, which is the opposite of what we find. We therefore attribute the apparent deficit of faint stars toward the crowded cluster center to *Gaia* incompleteness at $G \gtrsim 18$ mag rather than to a dynamical effect.

We estimated individual stellar masses and binary probabilities with ASteCA v0.6.9 (Fig. C.1). These values, particularly for PMS stars, should be interpreted with caution because the PMS CMD is poorly defined (Da Rio et al. 2010), which limits isochrone-based mass and binarity estimates. Binary probabilities of at least 0.6 define the binary class used throughout, consistent with the membership thresholds, while secondary masses are added to the system mass only for binary probability > 0.7 , a stricter cut that avoids inflating system masses through uncertain binary identifications.

Both the primary mass, m_1 , and the secondary mass, m_2 , are individual per-star estimates returned by ASteCA, not the product of an assumed universal mass ratio. For each of the 200 synthetic-cluster realizations drawn from the posterior of the fitted parameters, every observed star is matched to its photometrically nearest synthetic star, whose primary and (when the match is a binary) secondary masses are recorded; m_1 and m_2 are the medians of these values over the realizations, and the binary probability is the fraction of realizations in which the match is a binary. The mass ratios of the synthetic binaries follow the Duchêne & Kraus (2013) distribution introduced in Sect. 6.1; for the 51 stars whose secondary mass is added to the system mass (binary probability > 0.7), the resulting mass ratios span $q = m_2/m_1 = 0.26$ – 0.73 with a median of 0.60. The average mass of the stars is $1.31 \pm 0.10 M_\odot$ (standard error on the mean, combining the sampling and per-star mass uncertainties), computed as the total mass per system (summing both components for binary probability > 0.7) over the 254-source reference sample.

To investigate mass segregation, we constructed radial normalized cumulative mass distributions for single stars, binary stars, and the combination of both, as shown in Fig. 9. A two-sample KS test comparing binary and single stars yields $D = 0.221$ and $p = 0.010$, indicating that binary stars are significantly more centrally concentrated in the reference sample (but see the dependence on the outer candidates below). The signal is stable against the classification threshold ($D = 0.21$ – 0.29 , $p \leq 0.018$ for binary-probability cuts of 0.5–0.8) and is not solely a mass effect: restricting both classes to their overlapping mass range (0.37 – $2.77 M_\odot$) gives $D = 0.19$, $p = 0.07$, and a nearest-mass-matched comparison gives $D = 0.36$, $p < 0.001$; although the mass and binarity remain partially entangled. Across single-star mass quartiles the KS results vary ($D = 0.12$ – 0.33 , $p = 0.03$ – 0.86); given the width of these bins and the spread in p -values, we chose not to rely on any single quartile and, instead, we tested the segregation with the bin-free Λ_{MSR} analysis (Fig. 10), as described below.

To contextualize these findings, we calculated the half-mass relaxation time, t_{rh} (Spitzer 1969), which is crucial for estimating the minimum mass segregation time, t_{seg} . We adopted the standard form (Spitzer 1987, Eq. 2-63), expressed as

$$t_{\text{rh}} = \frac{0.138 N}{\ln(\gamma N)} \sqrt{\frac{r_{\text{hm}}^3}{GM}}, \quad (6)$$

where $N = 254$ is the size of the reference sample, $\gamma = 0.110$ is the equal-mass Coulomb-logarithm constant (not to

be confused with the HDBSCAN density level λ of Sect. 3.2; Giersz & Heggie 1994), and $r_{\text{hm}} = 2.02 \pm 0.41$ pc is the half-mass radius, derived from the radial cumulative mass distribution. For self-consistency between N and M , we ~~take took~~ M as the total observed mass of the same stellar system, $M = N\langle m \rangle = 332 \pm 26 M_\odot$, rather than a total cluster mass extrapolated from an assumed initial mass function. A normalization with the prefactor 0.17 also circulates in the open-cluster literature; it differs only in the assumed virial coefficient, $\langle v^2 \rangle r_{\text{hm}} / GM$ (the value 0.4 adopted here follows Spitzer & Hart 1971), and would lengthen t_{rh} by 23%, in the same direction as the mass-spectrum correction below. The adopted value is therefore the conservative one. The calculated half-mass relaxation time for NGC 6383 is 24.7 ± 7.6 Myr. For a system with a mass spectrum the effective Coulomb constant is smaller ($\gamma \approx 0.02$; Giersz & Heggie 1996), which would roughly double t_{rh} ; since all our dynamical-youth arguments rely on the cluster age being much shorter than t_{rh} , adopting the equal-mass value is the conservative choice. The dependence of γ on the mass spectrum is in fact available in closed form, as a functional of the mass function alone (Hénon 1975, Eqs. 11 and 26). Evaluating it on the observed mass distribution of the reference sample itself, holding N and M at the values above so that only γ changes, gives $\gamma \approx 0.05$, between the equal-mass and the multi-mass values quoted above, and a t_{rh} larger by a factor 1.27–1.35 (the range spanned by a kernel estimate of the mass function and by the discrete set of member masses), i.e., $t_{\text{rh}} \approx 31$ – 33 Myr. We retained $\gamma = 0.110$ throughout and carried this factor as a stated systematic: for the observed mass spectrum, it lengthens t_{rh} , and with it, t_{seg} and m_{lim} , so the values quoted below are conservative with respect to it.

Using the half-mass relaxation time, the timescale on which two-body relaxation drives a star of mass, m , toward the cluster center can be estimated following Spitzer (1969), expressed as

$$t_{\text{seg}}(m) = \frac{\langle m \rangle}{m} t_{\text{rh}}, \quad (7)$$

where $\langle m \rangle$ is the average stellar mass in the cluster: the more massive the star, the faster it segregates. For the most massive star of the reference sample ($13.56 \pm 3.25 M_\odot$) this yields the minimum segregation time of the cluster, $t_{\text{seg}} = 2.38 \pm 0.95$ Myr (propagating the uncertainties in $\langle m \rangle$, m , and t_{rh}); since this is shorter than the adopted cluster age, the most massive star has had time to segregate dynamically. The comparison is a marginal one rather than a strict inequality: the 1σ range of t_{seg} alone, 1.43–3.33 Myr, places the adopted age only 1.2σ above the central value, and the lower edge of the age range of Sect. 6.1 (2.24 Myr) falls slightly below the central t_{seg} . The mass-function value of γ discussed above moves t_{seg} the same way, to 3.0–3.2 Myr, and the multi-mass $\gamma \approx 0.02$ takes it to ≈ 4.9 Myr, above the mode age; the sign of this comparison, for the single most massive member, is therefore not robust against the choice of Coulomb constant. It does not affect the argument that follows, which rests on the stars whose t_{seg} exceeds the cluster age: a longer t_{rh} adds members to that set rather than removing them. This value directly depends on the mass of the most massive member and would decrease if HD 159176, which we do not retain as a member (Sect. 8.1), belonged to the cluster. Adopting the component masses of ≈ 44 – $46 M_\odot$ derived by Penny et al. (2016), t_{seg} of the most massive object would drop to ≈ 0.7 Myr (≈ 0.4 Myr if the binary is treated as a single $\sim 90 M_\odot$ body). This is a factor of 3–7 shorter and would only reinforce this conclusion.




Fig. 9. Radial cumulative distributions by mass and binarity. *Left panel:* Single stars in four mass quartiles, from $0.19\text{--}0.58 M_{\odot}$ to $1.44\text{--}13.56 M_{\odot}$. *Middle panel:* Same for binary stars, defined as sources with a binary probability of at least 0.6. *Right panel:* Single versus binary stars with masses between $0.19 M_{\odot}$ and $13.56 M_{\odot}$. In the left and middle panels the solid, dashed, dotted, and dash-dotted curves are the mass quartiles from lowest to highest; in the right panel single stars are solid and binary stars dashed. All panels use stars with a membership pseudo-probability of at least 0.6; the corresponding KS test results are given in Sect. 7.

For all other stars, Eq. (7) implies progressively longer segregation times. Setting $t_{\text{seg}}(m)$ equal to the cluster age defines a limiting mass, $m_{\text{lim}} = \langle m \rangle t_{\text{rh}}/t_{\text{age}}$, which for the mode age, $t_{\text{age}} = 3.53 \text{ Myr}$, and $\gamma = 0.110$ is $9.1 M_{\odot}$ (computed with unrounded posterior values); this is the value that defines the subsample used below. It is not a precise quantity. Across the age range of Sect. 6.1 it runs from $14.5 M_{\odot}$ at the young edge to $3.6 M_{\odot}$ at the old one, and the mass-function γ raises it by the factor given above at every age, to $11.6\text{--}12.4 M_{\odot}$ at the mode age. The argument is insensitive to this. Over that whole range the fraction of the reference sample below m_{lim} stays between 95% and 100%; the subsample itself is identical for any m_{lim} between 8.49 and $13.13 M_{\odot}$, a window that contains both the adopted value and its γ -corrected counterpart; and at the young edge m_{lim} exceeds the mass of the most massive member, so at that edge no member of the sample has t_{seg} shorter than the cluster age. Stars less massive than the adopted m_{lim} have t_{seg} longer than the cluster age, so two-body relaxation cannot yet have segregated them: any central concentration they exhibit must be primordial or early dynamical. If HD 159176 were included as a member, m_{lim} would shift only to $\approx 10.3 M_{\odot}$, leaving this subsample unchanged. We therefore repeated the analysis of Fig. 9 for the subsample with $m < m_{\text{lim}}$. This subsample comprises 252 of the 254 reference stars (99.2%) and spans $0.19\text{--}8.49 M_{\odot}$; only the two most massive members, of 13.13 and $13.56 M_{\odot}$, are excluded. The results (Fig. C.5) closely resemble Fig. 9, as expected for a nearly identical sample. Within this subsample the single-star quartile KS results range over $D = 0.12\text{--}0.36$ and $p = 0.01\text{--}0.84$, with the upper mass quartile ($1.41\text{--}8.49 M_{\odot}$) showing the largest separation. In this sample, the average mass is $1.21 \pm 0.08 M_{\odot}$. The distributions of single and binary stars are similar up to approximately 5 arcmin, beyond which single stars show less concentration compared to binary stars.

As an independent, bin-free check of mass segregation, we computed the mass-segregation ratio, Λ_{MSR} , of Allison et al. (2009b), which compares the minimum-spanning-tree (MST) length of the N_{MST} most massive members with that of random sets of the same size. This estimator needs no cluster center, and for smooth, centrally concentrated regions it agrees with the

other standard mass-segregation diagnostics (Parker & Goodwin 2015). We verified that NGC 6383 belongs to this regime rather than being spatially substructured by computing the structure parameter, Q , of Cartwright & Whitworth (2004) (the ratio of the normalized mean MST edge length to the normalized mean projected separation, not to be confused with the reddening-free index, Q , used above to identify YSOs). We obtain $Q = 1.03 \pm 0.03$ (bootstrap over the 254 reference-sample stars), well above the $Q \approx 0.8$ boundary separating centrally concentrated from fractal, substructured distributions, and consistent with the King concentration $C = 1.43$; we note that a proper-motion-selected, parallax-clipped sample is itself biased toward smooth configurations, so Q serves here as a consistency check rather than an independent morphology measurement. As shown in Fig. 10, Λ_{MSR} reaches $\approx 2.5\text{--}3.6$ for the 5–15 most massive members and decreases toward unity for larger samples, indicating that the most massive members are more centrally concentrated than typical members. We assessed the significance of this signal against an exact permutation null constructed on the observed member positions themselves, rather than against a null of exactly unity. Under the hypothesis that stellar mass is independent of position, the N_{MST} most massive stars occupy a uniform random N_{MST} -subset of the observed positions, which is precisely what the 500 reference sets already sample; the null distribution of Λ_{MSR} therefore follows from the same draws at no additional cost, and requires no assumption about the underlying radial profile. At the geometry of our reference sample the null median is 1.02 at $N_{\text{MST}} = 5$ rather than exactly 1, falling to unity for larger subsets, so the excess is measured from a slightly displaced origin. The strongest single point reaches a local $p \approx 5 \times 10^{-4}$; correcting for the eight values of N_{MST} examined, whose nesting yields a measured trials factor of about 7 rather than the naive 8, the scan-level significance is $p \approx 0.004$, i.e., $\approx 2.7\sigma$. This scan-level significance is unchanged if the members are ranked by primary mass instead of by system mass, which is the ranking cross-check required by the binary interpretation above, although the strongest individual point then falls at a different N_{MST} : the per-point significance is sensitive to the mass ranking, and the scan-level result is not. The signal is unchanged in di-

rection if the median edge length (Maschberger & Clarke 2011) or the geometric mean of the edge lengths (Olczak et al. 2011) replaces the total MST length, both of which limit the influence of a single long edge; the absolute values of the three variants are not directly comparable (Maschberger & Clarke 2011), so only their sign and relative behavior are compared here. The amplitude and significance of the signal, however, depend on the outer low-mass candidates of the reference sample, as expected for an estimator normalized by random members (Parker & Goodwin 2015): the ten most massive members lie at a median radius of about 4 arcmin in every sample below, so the contrast is set by how far the low-mass population extends. The 76 reference stars absent from the Hunt & Reffert (2024) membership lie at a median radius of 28.7 arcmin, have masses below $2.8 M_{\odot}$, and are mostly (67) classified as single. Restricting the sample to the 178 stars in common, or to $r < 15$ arcmin, keeps $\Lambda_{\text{MSR}} > 1$ at $N_{\text{MST}} = 5, 10, 15$, and 20 but lowers it to 1.1–2.0 (local $p = 0.02$ –0.35), and raises the p -value of the single-versus-binary KS test from 0.010 to ≈ 0.8 . Such restricted samples lack the extended low-mass population against which a central concentration of massive stars can be detected, so their null result does not by itself argue against segregation; the signal does, however, require the outer candidates to be members, which is not established. The flat background of the King fit to this sample, $b = 0.011 \pm 0.007$ stars arcmin $^{-2}$ (Table 1), corresponds to ≈ 55 of the 254 stars, is poorly constrained at 40 arcmin, and in a membership-selected sample can absorb an extended corona as well as contamination (as argued for the 70 arcmin fit in Appendix D). The fraction of Sagitta PMS candidates falls from 52% inside 10 arcmin to 27% at 20–40 arcmin. Removing the background implied by b at random, annulus by annulus (60 realizations, never removing the 20 most massive members), gives median local p -values for Λ_{MSR} of 0.001–0.03, 0.01–0.06, and 0.06–0.24, and for the KS test of 0.03, 0.13, and 0.46, for $b = 0.004, 0.011$, and 0.018 stars arcmin $^{-2}$, respectively; Λ_{MSR} stays above unity in all cases. The mass segregation of NGC 6383 is therefore conditional on the membership of its outer low-mass candidates, which radial velocities or additional youth indicators for those stars could settle; with these qualifications, this bin-independent result supports the signal seen in the cumulative distributions.

The cluster is dynamically young, with an age of only $\approx 0.14 t_{\text{th}}$, far below the ~ 2 – $3.5 t_{\text{th}}$ over which primordial mass segregation is erased in N -body models, including those with a realistic primordial binary population (Pavlík 2020). The intermediate-mass binaries that appear centrally concentrated in the reference sample have segregation times longer than the cluster age, so two-body relaxation is too slow to explain their distribution, suggesting instead that they formed closer to the center than single stars.

Two-body relaxation is not the only dynamical route, however: cool or substructured clusters can segregate rapidly through the transient dense core formed during an early collapse (Allison et al. 2009a), and subcluster merging accelerates segregation even in the low-membership regime of local open clusters such as NGC 6383 (Moeckel & Bonnell 2009). Such early dynamical segregation also erases substructure, leaving a smooth, concentrated remnant like the one observed here ($Q = 1.03$); it is therefore observationally degenerate with genuine birth segregation. We describe the central concentration as primordial or near-primordial, where near-primordial encompasses rapid early dynamical segregation during cluster assembly. Simulations show that this configuration can be inherited if the cluster assembled from clumps that were already mass-segregated, or segregated




Fig. 10. Mass-segregation ratio Λ_{MSR} (Allison et al. 2009b) of NGC 6383 as a function of the number of most-massive members N_{MST} . Following Allison et al. (2009b), $\Lambda_{\text{MSR}} = \langle l_{\text{norm}} \rangle / l_{\text{massive}}$ is the ratio of the mean minimum-spanning-tree length of 500 random N_{MST} -star sets to that of the N_{MST} most massive members (purple circles connected by a solid line); error bars are $\sigma_{\text{norm}} / l_{\text{massive}}$, following the convention of Allison et al. (2009b), and are not the quantity from which the significance quoted in Sect. 7 is derived. Values $\Lambda_{\text{MSR}} > 1$ indicate that the most massive stars are more centrally concentrated than random members; the gray dashed line marks $\Lambda_{\text{MSR}} = 1$ (no segregation).

before merging (McMillan et al. 2007), and can be amplified by residual-gas expulsion, which preferentially removes peripheral low-mass stars (Baumgardt & Kroupa 2007). A comparable primordial or near-primordial segregation is seen in other young clusters of similar age (Chen et al. 2007; Sabbi et al. 2008).

Population-level studies caution against a purely primordial reading for young open clusters: applying Λ_{MSR} and related indicators to 3881 *Gaia* DR3 clusters, Zhang (2026) finds the spatial segregation of < 10 Myr systems to be statistically consistent with random and attributes classical segregation to two-body relaxation only beyond ~ 100 Myr, and N -body models compared with observed open clusters similarly find primordial segregation not to be a decisive ingredient (Amiri et al. 2026). For NGC 6383 itself, Zhang et al. (2026) report no significant segregation of the five most massive stars ($\Lambda_{\text{MSR}} \approx 1$) in a 3D reconstruction of the high-probability Hunt & Reffert (2024) members, 90% of which lie within 6 arcmin of the center and therefore do not include the extended low-mass population on which our signal depends; we do not interpret their values below unity for the 10–20 most massive stars, because at this distance the parallax uncertainties of the bright members (0.02–0.03 mas) correspond to 26–36 pc along the line of sight, more than the 17 pc King outer radius. Our single-cluster, membership-conditional detection therefore does not by itself settle the primordial-versus-dynamical question; we report the segregation as measured and its origin as primordial or early dynamical.

8. Comparison with previous studies

We go on to compare the membership, structure, age, and dynamical state with previous work, proceeding from individual objects to catalogs: first the two stars whose membership is con-

8.1. HD 159176

HD 159176 is a double-lined O-type spectroscopic binary projected close to the center of NGC 6383 and is responsible for ionizing the surrounding HII region (Stickland et al. 1993; Linder et al. 2007; Penny et al. 2016). The estimated age of HD 159176 is 2.3–2.7 Myr (Rauw et al. 2010), in agreement with the earlier estimate of 2.8 ± 0.5 Myr (Fitzgerald et al. 1978). This estimate places the binary components, with the parameters of Linder et al. (2007), on single-star evolutionary tracks with and without rotation (Meynet & Maeder 2003), while the 2–3 Myr PMS ages of Rauw et al. (2010) rest on comparing X-ray-selected candidates with several PMS model families (e.g., Siess et al. 2000), and are therefore subject to the same code-dependent systematics discussed in Sect. 6.1. The two age ranges are compatible, consistent with a common star-formation event if the binary is assumed to be associated with the cluster.

In the study by Aidelman et al. (2018), it was hypothesized that if HD 159176 were a blue straggler, it would imply an older age for NGC 6383, ranging between 6.00 and 10.0 Myr. We do not use this assumption in the present analysis. HD 159176 is classified in the spectroscopic literature as a double-lined O-type main sequence binary, O7V((f))+O7V((f)) (Stickland et al. 1993; Linder et al. 2007) or O6.5V+O7V (Penny et al. 2016), and its thermal X-ray emission is attributed to the winds of the two O stars and their wind–wind interaction (Rauw et al. 2003; De Becker et al. 2004); no accretion-powered scenario has been proposed for this system.

The *Gaia* DR3 values of HD 159176 are $\varpi = 1.167 \pm 0.071$ mas, $\mu_{\alpha*} = 2.621 \pm 0.083$, and $\mu_{\delta} = -0.798 \pm 0.058$ mas yr⁻¹. These must be treated cautiously: at $G \simeq 5.7$ (vs $G_{\min} = 8.80$ and median $G \simeq 17.0$ for the reference sample) the star lies in the bright-source regime prone to saturation and magnitude-dependent astrometric systematics (Lindgren et al. 2021b,a; Cantat-Gaudin & Brandt 2021; Maíz Apellániz 2022). The $\mu_{\alpha*}$ agrees with the cluster mean and the parallax offset is not by itself conclusive; the strongest tension is in μ_{δ} , which differs from the cluster mean (-1.713 mas yr⁻¹, dispersion 0.138) by $\Delta\mu_{\delta} \simeq 0.91$ mas yr⁻¹, about 6σ once the star’s own proper-motion uncertainty is added in quadrature to the member dispersion. We note that the preprocessing parallax window (0.750–1.10 mas) already excludes the DR3 parallax of HD 159176, so its absence from the candidate sample is partly by construction; given the astrometric-quality caveats above, we read the μ_{δ} tension as supporting, rather than decisive, evidence against membership.

Gaia DR3 astrometric-quality indicators reinforce this: HD 159176 has a normal renormalized unit weight error (RUWE = 0.937), 13 visibility periods, and no duplicated-source flag, but an excess-noise significance of 135.6 and an image parameter determination (IPD) multi-peak fraction of 39, far above the reference-sample medians of zero (84th percentiles 1.53 and 0). These are not used as a membership criterion but confirm that HD 159176 must be treated as a special bright-source astrometric case (Rybicki et al. 2022).

We therefore exclude HD 159176 from the member sample used to characterize NGC 6383, its noteworthy projected central position notwithstanding. The age quoted for NGC 6383 in this paper is derived from the selected low-mass and PMS population and does not rely on the evolutionary status of HD 159176.

8.2. NGC 6383 22

NGC 6383 22⁹ is identified as a λ Boo star. These stars are chemically peculiar A-type stars with abundance anomalies attributed to the accretion of metal-poor material. In a spectroscopic survey of metal-weak and emission-line stars in the Southern Hemisphere, Murphy et al. (2020) found that λ Boo stars, including NGC 6383 22, exhibit excesses at longer wavelengths, suggestive of circumstellar disks. This characteristic aligns with other stars in NGC 6383 and those studied in Kalari (2019). However, NGC 6383 22 is not retained in our *Gaia*-selected member sample because, despite matching the position and parallax of the cluster, its proper motion ($\mu_{\alpha*} = 1.790 \pm 0.030$ mas yr⁻¹, $\mu_{\delta} = -2.710 \pm 0.024$ mas yr⁻¹) is more than 3σ away from the mean of the posterior distribution of μ . This result indicates that this star is likely passing near or through the cluster.

8.3. PMS studies using $H\alpha$ photometry and VPHAS+

Kalari (2019) examined 55 CTTS in the star-forming region Sh 2-012 and NGC 6383, utilizing VPHAS+ optical and $H\alpha$ photometry and *Gaia* astrometry. The reported mean age for these stars is 2.8 ± 1.6 Myr (the quoted uncertainty is the error on the mean; the dispersion of the individual ages is 3.4 Myr, with an interquartile range of 1.4–3.8 Myr), with masses between 0.3 and $0.9 M_{\odot}$ and a median mass of $0.5 M_{\odot}$. These ages and masses were obtained by interpolating the observed r versus $r - i$ CMD positions against PARSEC evolutionary models reddened by $E(B - V) = 0.32$ (Bressan et al. 2012). Kalari (2019) notes that the same data yield mean ages of 2.9 ± 1.7 and 3.5 ± 2.4 Myr with the Tognelli et al. (2011) and Siess et al. (2000) models, following the pattern reported by Herczeg & Hillenbrand (2015), so part of any difference from our MIST-based age reflects the choice of evolutionary code (Sect. 6.1). A second part reflects the adopted distance: Kalari (2019) adopts 1.34 kpc, from *Gaia* DR2 parallaxes, against our DR3-based 1.11 kpc. The two agree within 1.6σ , but the 0.41 mag difference in distance modulus places the same stars at a higher luminosity in that analysis and therefore biases the interpolated ages young relative to ours; the interpolated masses shift in the same direction. Notably, 94% of CTTS with near-infrared cross-matches conform to the near-infrared T-Tauri locus, and all stars with mid-infrared photometry showed signs of accreting circumstellar disks; the CTTS are concentrated around NGC 6383 and toward the bright rims of Sh 2-012.

Out of the 55 CTTS kinematic members of Sh 2-012, only 15 are cataloged as members or potential members of the cluster in this study, with most having a PMS probability over 0.6¹⁰. The difference in member selection is mainly methodological: Kalari (2019) selected CTTS primarily from photometric $H\alpha$ equivalent widths and then refined membership with a double-peaked Gaussian fit to the *Gaia* proper motions, whereas our selection rests on proper-motion clustering. Only one T-Tauri source¹¹ is likely a binary (0.94 probability according to our analysis); this source belongs to both our $\tilde{p} \geq 0.6$ reference sample and the Kalari (2019) CTTS list.

We also cross-matched our 321 likely candidates with the UBVR $H\alpha$ photometric catalog of Rauw et al. (2010). Using a 1.0 arcsec matching radius, we found 141 counterparts, including 124 sources from the $\tilde{p} \geq 0.6$ reference sample. Their CDS

⁹ Cataloged in SIMBAD as *Gaia* DR3 4054615634716139264.

¹⁰ The four exceptions have PMS probabilities of 16, 12, 55, and 45%.

¹¹ Cataloged as *Gaia* DR3 4054567805963940352.

table provides the $R_C-H\alpha$ index but not a published source-by-source $H\alpha$ emitter flag. We therefore do not treat the match as a recovery of the original Rauw et al. emitter list. Instead, we used their published $R_C-H\alpha$ color offsets (0.12–0.24 mag above the main sequence relation for candidates, > 0.24 mag for emitters) as a diagnostic relative to an empirical non-emitter locus derived from their catalog. Under this diagnostic classification, 51 of the 141 matched sources show $H\alpha$ excesses, including 28 of the 57 matched Sagitta PMS candidates. For the reference sample alone, 23 of the 51 matched Sagitta PMS candidates show such an excess. These matches support the presence of an emission-line subset among the PMS candidates, but the absence of diagnostic $H\alpha$ excess for the remaining PMS candidates is not decisive because Rauw et al. (2010) emphasized that $H\alpha$ emission is variable, can be weak for part of the PMS population, and that $H\alpha$ -selected samples can be contaminated by foreground and background objects.

8.4. Comparison with published catalogs

We compared our likely-candidate catalog (see also the historical compilation in Appendix A) with the catalogs from Cantat-Gaudin et al. (2020), Jaehnig et al. (2021), He et al. (2022), Hunt & Reffert (2024), and the members listed in SIMBAD. We find 148 sources in common with Cantat-Gaudin et al. (2020), 97 present only in their catalog, and 173 only in ours; 161 in common with Jaehnig et al. (2021) (123 only theirs, 160 only ours); 90 with He et al. (2022) (47 only theirs, 231 only ours); 202 with Hunt & Reffert (2024) (120 only theirs, 119 only ours); and 168 with SIMBAD (163 only there, 153 only ours). Because all rely at least partly on *Gaia* astrometry, the differences mainly reflect methodological choices, spatial windows, probability thresholds, and whether PMS or photometric information enters the selection. In particular, our selection clusters in the proper-motion plane only, whereas most catalog pipelines cluster in the full 3D to 5D astrometric space with their own probability floors and search radii, and SIMBAD aggregates heterogeneous literature memberships.

These overlaps also delimit the added value of the present analysis. These survey catalogs are homogeneous all-sky compilations optimized for thousands of clusters: for any individual cluster they provide a member list and bulk parameters derived from a single, fixed pipeline configuration. For NGC 6383, this work adds four elements. (i) Sampled posterior distributions, with reported uncertainties and convergence diagnostics, for the mean astrometric parameters, the parallax-based distance, and the King structural parameters, rather than pipeline point estimates; for the isochrone fit we report the ensemble together with the explicit statement that it has not converged (Sect. 3.1), and adopt an age range whose bounds are justified in the text instead of a posterior width, which is itself information a fixed-pipeline catalog does not provide. (ii) An explicit sensitivity budget for the main configuration choices, which none of the above catalogs quantify on a per-cluster basis: the HDBSCAN hyperparameter sweep is marginalized into the per-star pseudo-probabilities (Sect. 3.2, Appendix B), the dependence of the membership and structural parameters on the search window is measured directly (Appendix D), and the mass-segregation signal is checked for stability against the binary-classification threshold (Sect. 7). (iii) Cluster-specific analyses that survey pipelines do not attempt, namely the PMS census (Sagitta probabilities, ages, and extinctions; the YSO fraction; and the $H\alpha$ cross-match with Rauw et al. 2010), the dynamical-state analysis (t_{rh} , t_{seg} , Λ_{MSR}), per-star masses and binary probabilities, and the individual treat-

ment of HD 159176 as a bright-source astrometric special case. (iv) A per-star catalog at the CDS (Table 2) together with the open-source pipeline, which make the selection reproducible and its parameter dependence auditable.

Where a derived quantity does depend on a configuration choice (most notably the outer membership and the King outer radius with respect to the search window) we flag it explicitly as window- or model-dependent rather than reporting it as a robust measurement (Sect. 5, Appendix D). The survey catalogs remain the appropriate reference for homogeneous population-level comparisons across clusters; we regard the two approaches as complementary rather than competing.

The adopted King outer radius also merits comparison with the literature. Published outer or tidal radii for NGC 6383 span 15–30 arcmin (Table A.1), all smaller than our $R_t = 54^{+7}_{-11}$ arcmin, although the largest of them is consistent with it at the $\sim 2\sigma$ level. The difference is expected in direction: those determinations were limited either by extractions comparable to or smaller than the radii they report or by the depth of the underlying survey data, so, as in the case of our own 40 arcmin fit ($R_t = 40^{+16}_{-17}$ arcmin), their outer radii are limited by the available field, whereas our adopted value comes from the only extraction with a fitted background annulus beyond the cluster (Appendix D). The comparison therefore mostly reflects the window and background treatment, reinforcing our reading of R_t as a model- and prior-dependent outer scale, rather than a sharp physical boundary.

9. Conclusions

This study presents an analysis of the young open cluster NGC 6383, employing Bayesian analysis and machine-learning techniques to identify cluster members and determine key parameters. Using the HDBSCAN algorithm in proper-motion space followed by parallax clipping, we identified 321 likely cluster candidates with $\tilde{p} > 0.5$. The reference sample used for the cluster parameters contains 254 sources with membership pseudo-probabilities of at least 60%.

Our findings indicate that the cluster has a mode age of ≈ 3.5 Myr ($\log(\text{age yr}^{-1}) = 6.55^{+0.40}_{-0.20}$, the uncertainty being dominated by PMS model systematics that act toward older ages), with a distance of 1.11 ± 0.06 kpc derived from the parallax-based distance estimation. The core radius is $1.96^{+0.19}_{-0.16}$ arcmin; the King outer radius, measured on the 70 arcmin extraction, the only one whose profile reaches a fitted background annulus beyond the cluster, is 54^{+7}_{-11} arcmin, conditional on the prior bound that truncates its posterior from above (Sect. 5, Appendix D). Wider-field tests with 50, 60, and 70 arcmin input cones are able to recover an NGC 6383-like proper-motion branch and a consistent outer radius in all cases, but at 60 and 70 arcmin the automated branch selection no longer coincides with that branch, while the selected outer membership is not invariant with field size (Table D.2, Appendix D). In line with *Gaia*-based work on open-cluster structure and tidal features (Angelo et al. 2025; Risbud et al. 2025; Xu et al. 2025), R_t should therefore be regarded as a model-dependent scale rather than as an independently measured physical boundary.

The CMD analysis revealed a well-defined main sequence and a population of PMS stars, with the bulk of the PMS locus between the 1.6 and 6.3 Myr isochrones, consistent with a recent and possibly extended star-formation episode. The Sagitta neural network provided additional insights into the probabilities of PMS stars, their ages, and the extinction affecting cluster members. A cross-match with the UBVR $H\alpha$ catalog

of Rauw et al. (2010) identifies a diagnostic $H\alpha$ -excess subset among the matched PMS candidates, consistent with an emission-line or accreting component.

HD 159176 is projected near the cluster center, but its *Gaia* DR3 proper motion in declination is inconsistent with the selected cluster population; even allowing for the bright-source astrometric caveats discussed in Sect. 8.1, the tension is large enough that we exclude it from the member sample used for the cluster characterization. The age estimate reported here is derived from the selected PMS and low-mass population, as in previous PMS-based studies, and does not depend on assuming any particular evolutionary state for HD 159176.

If the outer low-mass candidates are members, the central concentration of binaries, even for those with segregation times longer than the cluster's age, suggests that they formed closer to the cluster center. This points to a primordial or early dynamical origin for the segregation. As discussed in Sect. 7, this reading is consistent with simulations of clump merging and gas expulsion and with the segregation observed in other young clusters, although population-level analyses have reported scarce statistically significant spatial segregation in clusters younger than ~ 10 Myr (Zhang 2026). Ultimately, our per-cluster result does not resolve this debate, and without the inclusion of those candidates, it is not significant (Sect. 7).

This work combines machine-learning membership with Bayesian parameter estimation to deliver an updated characterization of NGC 6383. It provides a template for similar studies of open-cluster candidates in the *Gaia* era. The software used in this study is available on GitHub¹² and the catalog is available at the CDS (see the section on data availability).

Data availability

The full version of Table 2 is only available in electronic form at the CDS via anonymous ftp to [cdsarc.u-strasbg.fr](ftp://cdsarc.u-strasbg.fr) (130.79.128.5) or via <http://cdsweb.u-strasbg.fr/cgi-bin/qcat?J/A+A/>. The EROTICA software used for this analysis is archived at <https://doi.org/10.5281/zenodo.21769959> and developed at <https://github.com/notluquis/erotica>.

Acknowledgements. This research has made use of the SIMBAD database and the VizieR catalogue access tool, operated at CDS, Strasbourg, France. We gratefully acknowledge support by the ANID BASAL project FB210003 and the SOCHIAS GEMINI project 32230014. L.P. gratefully acknowledges the invaluable comments and guidance of Dr. Robert Mathieu in the preparation of this investigation, and financial support from the Dirección de Postgrado, Universidad de Concepción, through the M.Sc. scholarship program. P.C. acknowledges the support of the UdeC VRID Iniciación fund 2025001386INI. This work has made use of data from the European Space Agency (ESA) mission *Gaia* (<https://www.cosmos.esa.int/gaia>), processed by the *Gaia* Data Processing and Analysis Consortium (DPAC, <https://www.cosmos.esa.int/web/gaia/dpac/consortium>). Funding for the DPAC has been provided by national institutions, in particular the institutions participating in the *Gaia* Multilateral Agreement. This publication makes use of data products from the Two Micron All Sky Survey, which is a joint project of the University of Massachusetts and the Infrared Processing and Analysis Center/California Institute of Technology, funded by the National Aeronautics and Space Administration and the National Science Foundation. The DSS2-red background image used in Fig. C.3 is based on the Digitized Sky Survey, produced at the Space Telescope Science Institute under U.S. Government grant NAG W-2166. This work made use of Astropy:¹³ a community-developed core Python package and an ecosystem of tools and resources for astronomy (Astropy Collaboration et al. 2013, 2018, 2022).

References

- Abril-Pla, O., Andreani, V., Carroll, C., et al. 2023, *PeerJ Computer Science*, 9, e1516
- Aidelman, Y., Cidale, L. S., Zorec, J., & Panei, J. A. 2018, *A&A*, 610, A30
- Allison, R. J., Goodwin, S. P., Parker, R. J., et al. 2009a, *ApJ*, 700, L99
- Allison, R. J., Goodwin, S. P., Parker, R. J., et al. 2009b, *MNRAS*, 395, 1449
- Amiri, V., Flammini Dotti, F., Pang, X., & Kouwenhoven, M. B. N. 2026, *arXiv e-prints*, arXiv:2606.04509
- Angelo, M. S., Santos, J. F. C., Corradi, W. J. B., & Maia, F. F. S. 2025, *MNRAS*, 539, 2513
- Asplund, M., Grevesse, N., Sauval, A. J., & Scott, P. 2009, *ARA&A*, 47, 481
- Astropy Collaboration, Price-Whelan, A. M., Lim, P. L., et al. 2022, *ApJ*, 935, 167
- Astropy Collaboration, Price-Whelan, A. M., Sipőcz, B. M., et al. 2018, *AJ*, 156, 123
- Astropy Collaboration, Robitaille, T. P., Tollerud, E. J., et al. 2013, *A&A*, 558, A33
- Bailer-Jones, C. A. L. 2015, *PASP*, 127, 994
- Bailer-Jones, C. A. L., Rybizki, J., Fouesneau, M., Demleitner, M., & Andrae, R. 2021, *AJ*, 161, 147
- Baraffe, I., Homeier, D., Allard, F., & Chabrier, G. 2015, *A&A*, 577, A42
- Battinelli, P. & Capuzzo-Dolcetta, R. 1991, *MNRAS*, 249, 76
- Baumgardt, H. & Kroupa, P. 2007, *MNRAS*, 380, 1589
- Becker, W. & Fenkart, R. 1971, *A&AS*, 4, 241
- Betancourt, M. 2016, *arXiv e-prints*, arXiv:1604.00695
- Betancourt, M. 2017, *arXiv e-prints*, arXiv:1701.02434
- Boubert, D. & Everall, A. 2020, *MNRAS*, 497, 4246
- Bovy, J. 2017, *MNRAS*, 468, L63
- Bressan, A., Marigo, P., Girardi, L., et al. 2012, *MNRAS*, 427, 127
- Buckner, A. S. M. & Froebrich, D. 2013, *MNRAS*, 436, 1465
- Cameron, E. 2011, *PASA*, 28, 128
- Campello, R. J. G. B., Moulavi, D., & Sander, J. 2013, in *Advances in Knowledge Discovery and Data Mining*, ed. J. Pei, V. S. Tseng, L. Cao, H. Motoda, & G. Xu (Berlin, Heidelberg: Springer Berlin Heidelberg), 160–172
- Cantat-Gaudin, T., Anders, F., Castro-Ginard, A., et al. 2020, *A&A*, 640, A1
- Cantat-Gaudin, T. & Brandt, T. D. 2021, *A&A*, 649, A124
- Cardelli, J. A., Clayton, G. C., & Mathis, J. S. 1989, *ApJ*, 345, 245
- Carrera, R., Pasquato, M., Vallenari, A., et al. 2019, *A&A*, 627, A119
- Cartwright, A. & Whitworth, A. P. 2004, *MNRAS*, 348, 589
- Castro-Ginard, A., Brown, A. G. A., Kostrzewa-Rutkowska, Z., et al. 2023, *A&A*, 677, A37
- Chabrier, G., Hennebelle, P., & Charlot, S. 2014, *ApJ*, 796, 75
- Chen, L., de Grijs, R., & Zhao, J. L. 2007, *AJ*, 134, 1368
- Choi, J., Dotter, A., Conroy, C., et al. 2016, *ApJ*, 823, 102
- Collinder, P. 1931, *Annals of the Observatory of Lund*, 2, B1
- Conrad, C., Scholz, R. D., Kharchenko, N. V., et al. 2017, *A&A*, 600, A106
- Da Rio, N., Gouliermis, D. A., & Gennaro, M. 2010, *ApJ*, 723, 166
- De Becker, M., Rauw, G., Pittard, J. M., et al. 2004, *A&A*, 416, 221
- de Grijs, R. & Bono, G. 2016, *ApJS*, 227, 5
- Dotter, A. 2016, *ApJS*, 222, 8
- Duchêne, G. & Kraus, A. 2013, *ARA&A*, 51, 269
- Eggen, O. J. 1961, *Royal Greenwich Observatory Bulletins*, 27, 61
- Evans, T. H. H. L. 1968, PhD thesis, Saint Andrews University, UK
- Feiden, G. A. 2016, *A&A*, 593, A99
- Feinstein, A. 1994, *Rev. Mexicana Astron. Astrofis.*, 29, 141
- Fitzgerald, M. P., Jackson, P. D., Luiken, M., Grayzeck, E. J., & Moffat, A. F. J. 1978, *MNRAS*, 182, 607
- Gaia Collaboration, Prusti, T., de Bruijne, J. H. J., et al. 2016, *A&A*, 595, A1
- Gaia Collaboration, Vallenari, A., Brown, A. G. A., et al. 2023, *A&A*, 674, A1
- Giersz, M. & Heggge, D. C. 1994, *MNRAS*, 268, 257
- Giersz, M. & Heggge, D. C. 1996, *MNRAS*, 279, 1037
- Graham, J. A. 1967, *MNRAS*, 135, 377
- He, Z., Wang, K., Luo, Y., et al. 2022, *ApJS*, 262, 7
- Hénou, M. 1975, in *IAU Symposium*, Vol. 69, *Dynamics of Stellar Systems*, ed. A. Hayli, 133
- Herczeg, G. J. & Hillenbrand, L. A. 2015, *ApJ*, 808, 23
- Hoffman, M. D. & Gelman, A. 2014, *Journal of Machine Learning Research*, 15, 1593
- Hunt, E. L. & Reffert, S. 2021, *A&A*, 646, A104
- Hunt, E. L. & Reffert, S. 2024, *A&A*, 686, A42
- Jaehnig, K., Bird, J., & Holley-Bockelmann, K. 2021, *ApJ*, 923, 129
- Kalari, V. M. 2019, *MNRAS*, 484, 5102
- Kharchenko, N. V., Piskunov, A. E., Röser, S., Schilbach, E., & Scholz, R. D. 2005, *A&A*, 438, 1163
- Kharchenko, N. V., Piskunov, A. E., Schilbach, E., Röser, S., & Scholz, R. D. 2013, *A&A*, 558, A53
- King, I. 1962, *AJ*, 67, 471
- Kounkel, M., Covey, K., & Stassun, K. G. 2020, *AJ*, 160, 279
- Kounkel, M., Stassun, K. G., Hillenbrand, L. A., et al. 2023, *AJ*, 165, 182

¹² <https://github.com/notluquis/erotica>

¹³ <http://www.astropy.org>

- Lindgren, L., Bastian, U., Biermann, M., et al. 2021a, A&A, 649, A4
- Lindgren, L., Klioner, S. A., Hernández, J., et al. 2021b, A&A, 649, A2
- Linder, N., Rauw, G., Sana, H., De Becker, M., & Gosset, E. 2007, A&A, 474, 193
- Lindoff, U. 1968, Arkiv for Astronomi, 5, 1
- Lloyd Evans, T. 1978, MNRAS, 184, 661
- Maíz Apellániz, J. 2022, A&A, 657, A130
- Marigo, P., Girardi, L., Bressan, A., et al. 2017, ApJ, 835, 77
- Marrese, P. M., Marinoni, S., Fabrizio, M., & Altavilla, G. 2022, Gaia DR3 documentation Chapter 15: Cross-match with external catalogues, Gaia DR3 documentation, European Space Agency; Gaia Data Processing and Analysis Consortium. Online
- Maschberger, T. & Clarke, C. J. 2011, MNRAS, 416, 541
- Mathis, J. S. 1990, ARA&A, 28, 37
- McBride, A., Lingg, R., Kounkel, M., Covey, K., & Hutchinson, B. 2021, AJ, 162, 282
- McInnes, L., Healy, J., & Astels, S. 2017, The Journal of Open Source Software, 2, 205
- McMillan, P. J. 2017, MNRAS, 465, 76
- McMillan, S. L. W., Vesperini, E., & Portegies Zwart, S. F. 2007, ApJ, 655, L45
- Meynet, G. & Maeder, A. 2003, A&A, 404, 975
- Moe, M. & Di Stefano, R. 2017, ApJS, 230, 15
- Moeckel, N. & Bonnell, I. A. 2009, MNRAS, 400, 657
- Morales, E. F. E., Wyrowski, F., Schuller, F., & Menten, K. M. 2013, A&A, 560, A76
- Murphy, S. J., Gray, R. O., Corbally, C. J., et al. 2020, MNRAS, 499, 2701
- O'Donnell, J. E. 1994, ApJ, 422, 158
- Offner, S. S. R., Moe, M., Kratter, K. M., et al. 2023, in Astronomical Society of the Pacific Conference Series, Vol. 534, Protostars and Planets VII, ed. S.-i. Inutsuka, Y. Aikawa, T. Muto, K. Tomida, & M. Tamura, 275
- Olczak, C., Spurzem, R., & Henning, T. 2011, A&A, 532, A119
- Pandey, A. K., Bhatt, B. C., Mahra, H. S., & Sagar, R. 1989, MNRAS, 236, 263
- Parker, R. J. & Goodwin, S. P. 2015, MNRAS, 449, 3381
- Paunzen, E., Netopil, M., & Zwintz, K. 2007, A&A, 462, 157
- Pavlík, V. 2020, A&A, 638, A155
- Pedregosa, F., Varoquaux, G., Gramfort, A., et al. 2011, Journal of Machine Learning Research, 12, 2825
- Penny, L. R., Epps, J. G., & Snyder, J. D. 2016, ApJ, 832, 211
- Perren, G. I., Pera, M. S., Navone, H. D., & Vázquez, R. A. 2023, MNRAS, 526, 4107
- Perren, G. I., Vázquez, R. A., & Piatti, A. E. 2015, A&A, 576, A6
- Peterson, C. J. & King, I. R. 1975, AJ, 80, 427
- Pinfield, D. J., Jameson, R. F., & Hodgkin, S. T. 1998, MNRAS, 299, 955
- Piskunov, A. E., Schilbach, E., Kharchenko, N. V., Röser, S., & Scholz, R. D. 2008, A&A, 477, 165
- Pulgar-Escobar, L. M. & Henríquez-Salgado, N. A. 2024, Boletín de la Asociación Argentina de Astronomía La Plata Argentina, 65, 146
- Rauw, G. & De Becker, M. 2008, in Handbook of Star Forming Regions, Volume II, ed. B. Reipurth, Vol. 5 (Astronomical Society of the Pacific), 497
- Rauw, G., De Becker, M., Gosset, E., Pittard, J. M., & Stevens, I. R. 2003, A&A, 407, 925
- Rauw, G., Manfroid, J., & De Becker, M. 2010, A&A, 511, A25
- Risbud, D., Jadhav, V. V., & Kroupa, P. 2025, A&A, 694, A258
- Rybizki, J., Green, G. M., Rix, H.-W., et al. 2022, MNRAS, 510, 2597
- Sabbi, E., Sirianni, M., Nota, A., et al. 2008, AJ, 135, 173
- Sanford, R. F. 1949, ApJ, 110, 117
- Sharpless, S. 1959, ApJS, 4, 257
- Siess, L., Dufour, E., & Forestini, M. 2000, A&A, 358, 593
- Skrutskie, M. F., Cutri, R. M., Stiening, R., et al. 2006, AJ, 131, 1163
- Somers, G., Cao, L., & Pinsonneault, M. H. 2020, ApJ, 891, 29
- Somers, G. & Pinsonneault, M. H. 2015, ApJ, 807, 174
- Spitzer, L. 1987, Dynamical evolution of globular clusters (Princeton University Press)
- Spitzer, Jr., L. 1969, ApJ, 158, L139
- Spitzer, Jr., L. & Hart, M. H. 1971, ApJ, 164, 399
- Stickland, D. J., Koch, R. H., Pachoulakis, I., & Pfeiffer, R. J. 1993, The Observatory, 113, 204
- ter Braak, C. J. F. 2006, Statistics and Computing, 16, 239
- The, P. S., Hageman, T., Westerlund, B. E., & Tjin-A-Djie, H. R. E. 1985, A&A, 151, 391
- Tognelli, E., Prada Moroni, P. G., & Degl'Innocenti, S. 2011, A&A, 533, A109
- Trumpler, R. J. 1930, Lick Observatory Bulletin, 420, 154
- van den Ancker, M. E., Thé, P. S., & de Winter, D. 2000, A&A, 362, 580
- Vehtari, A., Gelman, A., Simpson, D., Carpenter, B., & Bürkner, P.-C. 2021, Bayesian Analysis, 16, 667
- Xu, M., Fu, X., Chen, Y., et al. 2025, A&A, 698, A156
- Zhang, S. 2026, AJ, 171, 236
- Zhang, S., Deng, Z., Zhao, W., Chi, H., & Chen, J. 2026, AJ, 172, 85

Appendix A: Historical parameters of NGC 6383

Table A.1 compiles the structural and fundamental parameters of NGC 6383 reported in the literature since Trumpler (1930). The wide spread of historical core and tidal radii, distances, reddenings, distance moduli, and ages, obtained with heterogeneous data and methods over nearly a century, illustrates the lack of a homogeneous determination and motivates the *Gaia*-based reanalysis presented in this work. For each study we list only the quantities explicitly reported; ellipses denote parameters not provided.

Table A.1. Literature parameters of NGC 6383.

Reference	Members	Core radius (arcmin)	Tidal radius (arcmin)	Parallax (mas)	Distance (kpc)	$E(B - V)$ (mag)	$(m - M)$ (mag)	Age (Myr)
Trumpler (1930)	...	...	...	...	2.13	...	...	...
Sanford (1949)	...	...	...	...	0.76	...	...	...
Eggen (1961)	...	...	...	...	...	0.30	...	...
Graham (1967)	74	...	...	...	1.38	...	10.7±0.5	...
Evans (1968)	At least 21	...	...	...	1.30	0.35	10.6	5.0
Lindoff (1968)	...	...	...	...	1.25	...	10.5	~ 20
Becker & Fenkart (1971)	...	...	...	...	1.07	0.26	10.9	...
Fitzgerald et al. (1978)	...	1.25	...	...	1.50±0.20	0.33±0.02	10.9	1.7±0.4
Lloyd Evans (1978)	...	...	...	...	1.35	0.35	10.6	Up to 5.0
The et al. (1985)	...	...	...	...	1.40±0.15	0.30±0.01	...	...
Pandey et al. (1989)	...	...	...	...	...	0.35	11.7	~ 4.5
Battinelli & Capuzzo-Dolcetta (1991)	27	...	...	...	1.38	0.34	...	~ 20
Feinstein (1994)	...	...	...	...	1.40	0.33	...	...
Rauw et al. (2003)	...	...	...	...	...	0.33	10.7	...
Kharchenko et al. (2005)	13	4.80	15.0	...	0.99	0.30	10.9	5.0
Paunzen et al. (2007)	...	...	...	...	1.70±0.30	0.29±0.05	...	Less than 4.0
Piskunov et al. (2008)	...	...	29.0±4.2	...	0.99	0.30	10.9	5.0
Rauw et al. (2010)	55 PMS candidates	...	...	...	...	0.32	...	2–3
Aidelman et al. (2018)	...	...	...	...	0.83±0.16	0.51±0.03	9.61±0.38	~3–10
Kalari (2019)	At least 55	...	...	...	1.34±0.13	0.32	...	2.8±1.6
Jaehnig et al. (2021)	284	...	...	0.93±0.09	1.07	...	...	...
He et al. (2022)	...	...	...	0.88±0.05	...	0.45	...	3.5
Hunt & Reffert (2024)	322	2.49	22.7	0.89±0.08	1.10	0.39	10.2	~ 4.0
Pulgar-Escobar & Henríquez-Salgado (2024)	266	1.21±0.13	29.7±7.7	0.92±0.06	1.10±0.04	0.47±0.03	10.9±0.33	~1–4

Notes. For He et al. (2022), Hunt & Reffert (2024), and Pulgar-Escobar & Henríquez-Salgado (2024), which publish A_0 or A_V , $E(B - V)$ is A_V/R_V (or A_0/R_V) with $R_V = 3.1$. The literature tidal radii are King tidal radii, here denoted the King outer radius R_t , except Kharchenko et al. (2005), whose value is their empirical cluster (corona) radius; the Piskunov et al. (2008) value is their r_t (8.3 ± 1.2 pc at their adopted distance). The ages are not derived on a common distance scale: the distances adopted by the studies that report an age span 0.83–1.70 kpc, a range of 1.6 mag in distance modulus, and an age obtained by placing stars on evolutionary tracks moves systematically with that choice. The listed ages should therefore be compared with the corresponding distance, not in isolation.

Appendix B: HDBSCAN diagnostic and ASteCA isochrone-fit corner plots

This appendix documents the unsupervised-clustering diagnostics and the isochrone-fit ensemble that underpin the membership and parameter determinations of Sects. 3 and 6.1. We first describe how the HDBSCAN configuration was selected from the proper-motion clustering sweep (Figs. B.1 and B.2), show the resulting clustering of the full sample in the proper-motion plane and on the sky (Fig. B.3), and then present the joint distribution of the ASteCA isochrone fit (Fig. B.4).

HDBSCAN was run over the grid $m_{cl} = 10, \dots, 299$ in the 2D proper-motion plane, setting `min_cluster_size=min_samples= $m_{cl}$` and using the leaf cluster-selection method (Sect. 3.2). For each run we recorded the size of the recovered NGC 6383 branch (the condensed-tree branch containing the highest density level, λ_{max} ; Sect. 3.2) and its λ_{max} . Figure B.1 displays the runs in the stable regime, delimited by $\lambda_{max} \geq 8$ and a recovered branch of 200–701 sources (the upper bound being the largest branch recovered in the sweep); below $\lambda_{max} = 8$ the condensed tree is too shallow to separate the cluster from the field. These display cuts do not enter the selection: as Fig. B.1 shows, the recovered branch size peaks at the adopted $m_{cl} = 43$, with smaller m_{cl} fragmenting the cluster into spurious subgroups and larger m_{cl} progressively merging field stars into the branch or dissolving it altogether.




Fig. B.1. Cluster size variation as a function of minimum cluster size, determined through HDBSCAN clustering on the proper-motion data of the sources. The blue line shows the recovered cluster size; the dashed blue line marks the adopted minimum cluster size of 43, where the cluster size peaks, and the dashed green line the maximum observed cluster size of 701. Only sweep runs in the stable regime ($\lambda_{max} \geq 8$ and recovered branch of 200–701 sources) are shown, which is why the axis does not span the full $m_{cl} = 10$ –299 grid; this display cut does not enter the selection of m_{cl} .




Fig. B.2. Condensed cluster tree (dendrogram) from the HDBSCAN analysis: NGC 6383 cluster sources on the left, HDBSCAN-identified field sources on the right. Branch width and color give the number of sources at each level (color bar); $\lambda = 1/d_{\text{mreach}}$ is the inverse mutual-reachability distance. Colored ellipses mark the leaf clusters selected by HDBSCAN; the tall blue ellipse on the left, persisting over the widest λ range, is the branch adopted as NGC 6383.

the main text. The intervals quoted for these parameters in the main text and in Table 1 are the marginal spreads of this ensemble; for the reasons just given they are indications of scale rather than calibrated credible widths, as the notes to that table state. The term σ is retained only as a fit nuisance parameter and carries no physical meaning.

The condensed cluster tree (Fig. B.2) displays the HDBSCAN hierarchy as a function of the density level, $\lambda = 1/d_{\text{mreach}}$, where wider and more persistent branches correspond to denser, more significant over-densities. The NGC 6383 branch (the tall blue ellipse on the left) persists over the widest λ interval and is clearly detached from the field branches on the right, providing the qualitative counterpart of the quantitative stability criterion used in Fig. B.1. This persistence is what allows the proper-motion over-density of NGC 6383 to be selected unambiguously, despite the known tendency of HDBSCAN to report spurious dense fluctuations in noisy data (Hunt & Reffert 2021).

Figure B.3 places the selected branch in context, showing the full 40 arcmin preprocessed sample (15276 sources) labeled by HDBSCAN, both in the proper-motion plane and on the sky. In proper motion, NGC 6383 forms a compact, well-isolated over-density around $(\mu_\alpha^*, \mu_\delta) = (2.5, -1.7) \text{ mas yr}^{-1}$, clearly separated from the diffuse field and from the other, more dispersed HDBSCAN branches. On the sky, by contrast, the three groups overlap, with only a mild central concentration of the cluster members. This confirms that the membership signal is carried by the proper motions rather than by projected position, justifying the proper-motion-only clustering feature space adopted in Sect. 3.2.

Figure B.4 shows the joint and marginal distributions of the four ASteCA isochrone-fit parameters together with the likelihood-scatter nuisance term, σ , sampled with the DEMetropolis ensemble (Sect. 6.1). The marginals are single-peaked but only weakly informative: each retains a large fraction of its prior width, and the ensemble does not satisfy the convergence criteria of Sect. 3.1, so they should be read as a consistency check rather than as sampled posteriors. The off-diagonal panels make the classical CMD-fitting degeneracies explicit: logarithmic age correlates with both visual extinction and distance modulus, so that an older age can be partially compensated by a lower extinction or a smaller distance. Metallicity is the least constrained parameter and remains close to prior-dominated, consistent with the age–metallicity–extinction degeneracy noted in




Fig. B.3. Full HDBSCAN clustering panorama of the 40 arcmin preprocessed sample (15276 sources). *Left panel:* Proper-motion plane (μ_α^*, μ_δ). *Right panel:* On-sky distribution in right ascension and declination. Sources are color-coded by their HDBSCAN label: the selected NGC 6383 branch (red), the other HDBSCAN branches (blue), and the field/noise (gray); the legend lists the number of sources in each group. The proper-motion axes are clipped to the 0.5–99.5 percentile range so that the cluster over-density-overdensity is visible against the broad field distribution.




Fig. B.4. Marginal and joint distributions of the parameters A_V (visual extinction, for a fixed $R_V = 3.1$), dm (distance modulus), $\log a$ (logarithmic age), met (metallicity), and the nuisance likelihood-scatter parameter σ , sampled with the DEMetropolis ensemble. The diagonals display the marginal distributions for each parameter (blue curves). The off-diagonal hexbin plots show the joint distributions. Black lines mark the mode of each distribution in all panels; in the off-diagonal panels, the joint mode is additionally marked by a black square.

Appendix C: Supplementary figures

This appendix collects the supplementary figures referenced from the main text: the masses and binarity CMD (Fig. C.1); the luminosity function derived from absolute magnitudes (Fig. C.2); the on-sky distribution of the members with the derived scale radii overlaid on the DSS2-red image (Fig. C.3); the per-star Sagitta PMS-probability, age, and extinction distributions (Fig. C.4); the mass-segregation cumulative distribu-

tions for the segregation-time-restricted sample (Fig. C.5); and the *Gaia* DR3 radial velocities and their amplitudes (Fig. C.6). These figures support, but are not essential to, the results presented in the main text.




Fig. C.1. *Left panel:* CMD displaying probable members and members of NGC 6383, color-coded by total mass, ranging from lower (yellow) to higher mass (purple). The total mass is calculated as the sum of the two components if the binary probability is greater than 0.7. *Right panel:* Same stars as in the left panel, color-coded by binary probability, from low (yellow) to high (purple). The dark-gray dashed line in both panels is the best mode-fit isochrone.




Fig. C.2. Luminosity function of NGC 6383: histogram (orange, hatched) of absolute magnitudes (G_{abs}) for stars with a membership pseudo-probability of at least 0.6.




Fig. C.3. Spatial distribution of probable members and members (dark-red dots) overlaid on a DSS2-red background image (shown in false color), centered on the derived cluster center marked by a blue marker. The circles are the 40 arcmin cone-search radius and, in increasing order of size, the fitted or derived scale radii R_c , R_{hl} , R_{hm} , R_{hill} , and R_{bound} , whose values are given in the legend. The adopted King outer radius ($R_t = 54$ arcmin, Appendix D, Fig. D.1) lies just outside the displayed field and is not drawn.




Fig. C.4. Histograms of the parameters obtained with Sagitta for the NGC 6383 reference sample ($\bar{p} \geq 0.6$), including all data (gray solid), sources with a PMS probability of at least 60% (orange solid), sources with a PMS probability under 60% (blue dashed), and stars with missing 2MASS data (green dotted); the legend in the middle panel applies to all panels. The left panel shows the distribution of PMS probability values; the middle panel presents the distribution of logarithmic age values; and the right panel displays the distribution of visual extinction values (A_V).




Fig. C.5. Same as Fig. 9, but restricted to stars whose segregation time exceeds the cluster age ($t_{\text{seg}}(m) > 3.53$ Myr, i.e., $m < 9.1 M_\odot$; Sect. 7); the mass quartiles are recomputed for this truncated sample (uppermost quartile 1.41–8.49 $M_\odot$).




Fig. C.6. Radial velocity versus G magnitude for the 29 reference-sample sources with *Gaia* DR3 radial velocities. Filled circles have DR3 amplitude measurements (`rv_amplitude_robust`, which reflects the total amplitude in the radial-velocity time series following outlier removal) and are color-coded by amplitude (viridis color bar); open gray diamonds lack amplitude measurements. Vertical bars show the radial-velocity uncertainties.




Fig. D.1. Radial density profile of the 70 arcmin extraction ($N = 628$, $\bar{p} \geq 0.6$; black circles) with the King model at the posterior median (blue solid line) and its 16–84% posterior band (blue shading). The black dotted vertical line marks the adopted King outer radius ($R_t = 54$ arcmin) and the gray dash-dotted horizontal line the fitted background level, b .

Appendix D: Search-window sensitivity of the derived parameters

This appendix complements the membership-recovery counts of Table D.1 by listing, side by side, the astrometric and structural parameters recovered at each input cone-search radius. Only the membership, astrometric, and King-structural quantities were re-computed for the wider fields; the photometric quantities (ages, masses, and the mass-segregation diagnostics) remain tied to the 40 arcmin reference catalog and are not repeated per radius. As discussed in Sect. 3.3, the catalog-level astrometry is stable across radii, whereas the structural parameters and the outer-membership counts drift once the automated branch selection becomes field-window dependent (at 60 and 70 arcmin).

The 70 arcmin window provides the adopted King outer radius (Sect. 5). The probability that R_t exceeds the extraction window decreases from 51% at 40 arcmin to 40% and 13% at 50 and 60 arcmin (at 70 arcmin it vanishes by construction, since the prior support ends at $1.5 T_{\max} = 63.7$ arcmin), and Fig. D.1 shows that only this window reaches a well-defined background annulus beyond the cluster, with fitted background $b = 0.020^{+0.006}_{-0.010}$ and central density $k = 8.42 \pm 0.17$ stars per square arcminute. All R_t posteriors, including the adopted one, are truncated from above by the physically motivated $1.5 T_{\max}$ prior bound and remain conditional on it; the shift under a relaxed bound is quantified in Sect. 5. The background of this membership-selected sample is not the raw field density but a fitted constant absorbing whatever lies beyond the profile: residual contamination of the selection, an extended corona, or populations overlapping the cluster in projection. Distinguishing them requires diagnostics beyond co-motion and projected radius (Risbud et al. 2025; Xu et al. 2025), which we do not attempt here. The core radius and central density of the 70 arcmin fit are contamination-biased (Sect. 3.3) and are not adopted. The two parameters are constrained by different parts of the profile. The core radius, R_c , is set by the inner density, which the 60 and 70 arcmin windows lower to ≈ 1.4 arcmin while the selection-

stable 50 arcmin run reproduces the adopted value (Table D.2); R_t is set by where the profile meets a fitted background annulus, which only the 70 arcmin window provides. We therefore adopted each from the window that constrains it. The King outer radius, R_t , is not thereby immune to the composition of the wider sample: it remains conditional on the prior bound, and the concentration parameter, C , combines posteriors from two fits to two samples.

Table D.1. Robustness of the membership recovery against the input cone-search radius.

Radius (arcmin)	Preprocessed sources	Best m_{cl}	Algorithm label	NGC-like label	NGC branch size	$\tilde{p} > 0.5$ after clip	$\tilde{p} \geq 0.6$ reference sample	Common with adopted 254
40	15276	43	0	0	701	321	254	254
50	23844	18	28	28	767	355	236	203
60	33309	143	1	0	696	476	443	242
70	44438	177	1	0	798	650	628	252

Notes. The 40 arcmin row is the production catalog used for the adopted cluster parameters, while the 50–70 arcmin rows are wider-field robustness checks. Each run used the same preprocessing, the same proper-motion-only HDBSCAN feature space, the same pseudo-probability construction as in Sect. 3.2, and the same parallax-mode sigma clipping. The algorithm-selected branch is the branch selected by the generic sweep rule, while the NGC-like branch is the final HDBSCAN label closest to the reference proper motion of NGC 6383, $(\mu_{\alpha*}, \mu_{\delta}) = (2.542, -1.713)$ mas yr⁻¹.

Table D.2. Astrometric and King-structural parameters recovered at each input cone-search radius.

Radius (arcmin)	N ($\tilde{p} \geq 0.6$)	$\bar{\varpi}$ (mas)	$\mu_{\alpha*}$ (mas yr ⁻¹)	μ_{δ} (mas yr ⁻¹)	R_c (arcmin)	R_t (arcmin)	C	$P(R_t > W)$ (%)
40	254	0.908 ± 0.046	2.542 ± 0.152	-1.713 ± 0.138	$1.96^{+0.19}_{-0.16}$	40^{+16}_{-17}	$1.32^{+0.16}_{-0.27}$	51
50	236	0.906 ± 0.044	2.544 ± 0.133	-1.711 ± 0.127	$1.90^{+0.15}_{-0.13}$	46^{+12}_{-16}	$1.39^{+0.11}_{-0.20}$	40
60	443	0.916 ± 0.051	2.455 ± 0.239	-1.693 ± 0.159	$1.36^{+0.10}_{-0.09}$	47^{+12}_{-16}	$1.54^{+0.10}_{-0.19}$	13
70	628	0.915 ± 0.057	2.383 ± 0.279	-1.680 ± 0.163	$1.38^{+0.04}_{-0.04}$	54^{+7}_{-11}	$1.59^{+0.06}_{-0.11}$	0

Notes. The 40 arcmin row is the adopted production fit; the 50–70 arcmin rows use the same King priors applied to the wider-field reference samples. [Here](#), N is the number of reference-sample candidates ($\tilde{p} \geq 0.6$). The mean parallax, $\bar{\varpi}$, is quoted with the 1σ dispersion of the subsample with $\delta\varpi/\bar{\varpi} < 0.1$; the proper-motion means carry the 1σ member dispersions. The core radius R_c , King outer radius R_t , and concentration $C = \log_{10}(R_t/R_c)$ are the posterior medians with 16–84% credible intervals of the King fit; $P(R_t > W)$ is the posterior probability that R_t exceeds the extraction window. Ages, masses, and mass segregation were not recomputed per radius (see text).